Status of Aerogel detector for high pT upgrade at PHENIX

Budget from US-J project for next two years:

- (1) 400 liters of Aerogel
- (2) 600 photomultiplier tubes
- (3) read-out electronics
- (4) detector construction
- (5) one additional TOF panel


Preliminary design

12x12x10 cm³, 300 segmentations, 2 tubes each 2x2 m² (4 TOF panels) at r=4.5m in west arm

Laser test for Aerogel optical properties determine $\lambda_{absorption}$, $\lambda_{scattering}$ for the different wave length and the index of Aerogel


Beam test with several prototypes at KEK-PS
Belle type (2 PMTs directly on both sides of Aerogel)
Mirror type (mirror and PMT behind of Aerogel)
reflective material, thickness, position, angle
and momentum dependence


Simulation study with pisa 5% occupancy with Hijing central Au+Au (20% for all the charged tracks)




compare measurements and <code>optical monte-carlo</code> to determine λ $_{absorption}$, λ $_{scattering}$ with χ^2 minimization


Beam test at KEK-PS, 2001/Dec










Туре	Reflector	Index	Mom. (GeV)	N _{photo-ele} (PMT1) (R6233.1500V)	N _{photo-ele} (PMT2) (R6233.1500V)
Belle	Goretex	1.018	3	12	13
Belle	Millipore	1.018	3	9	10
Belle	Tyvek	1.018	3	8	8
Mirror (Flat)	Tyvek	1.018	3	9	
Mirror (Parabolic)	Tyvek	1.018	3	9	








PISA simulation with Aerogel



-250 L

x (cm)




Aerogel counter prototype in the test beam line at KEK-PS 2001/Dec

Konno, Ohki







Aerogel in a Belle prototype

Aerogel counter simulation

Takagi

Summary of status

(1) definition of the project

- *to enhance PID capability of PHENIX upto 10GeV/c with Aerogel, TOF and RICH
- *~400 liters of Aerogel with ~300 segmentation, which is 4 TOF panels equivalent

(2) Detector R&D

- *2001/Dec test experiment at KEK-PS
- *Belle/mirror types are tested, the best result (>20pe) is with Belle type with 3"PMT and Goetex reflector.
- *Next test beam is planned before 2002/Summer.
- *Detailed study for the absorption and scattering length as a function of wave length with laser and spectrometer is in progress.

(3) PISA simulation

- *PISA simulation activity has been started at Tsukuba, ~300 Aerogel counters have been installed in west arm.
- *Occupancy and background studies have been started.

(4) Budget and construction

- *Purchase of Aerogel and PMTs with US-J budget will be started in 2002 and finished in 2003.
- *Dubna may be interested in the construction of detector, Y.Miake will visit Dubna in March for further discussion.

(5) Issues and concerns

- *2 TOF panels will be moved from east arm to west. 1 spare panel exists at BNL. 1 panel will be newly build.
- *Read-out electronics designed for RICH will be copied, but it needs to be studied in detail.