

# *Si-W Forward Calorimeters*

*(Nosecone Calorimeter "NCC")*


## *Mechanical System & Integration*

*Don Lynch*


# NCC Detector Mechanical Tasks

- Define space allocation - BNL
- Detector module mechanical design - BNL
- Internal structural support/assembly - BNL
- Detector Fabrication - BNL+JINR+....
- External mechanical/structural support - BNL
- Services (cables, cooling, etc.) - BNL
- Installation/alignment concept and logistical support - BNL

# CM Region Space Allocation



# CM Region 3D Space Allocation




All space in between the CM poles to a radius of 2 meters from the nominal beam centerline has been (or will be) apportioned to the north and south NCC and east and west VTX/FVTX detectors, with allowances for common support infrastructure

Groups working on the VTX, FVTX and NCC have been coordinating space allocation on a regular basis.

Since the HBD in the outboard position has been abandoned, The space previously allocated to the HBD is now unoccupied space.



# Current CM Region



Currently the HBD and RXNP detectors are installed in this region. They will remain there until the NCC and/or the VTX is ready for installation.


Support infrastructure and cable management support for HBD may be reused by VTX/FVTX. NCC support structure will be integrated into the NCC design.

# Mechanical Design Concept






# Typical NCC Module Design

## EM Section



Position sensitive detectors



## Hadronic Section


HAD PART 102 mm

EM PART 83.0mm




Don Lynch

# Mechanical Assembly Concept



# Thermal Considerations



Preamp module, 1 per brick  
each generate ~ 150 watts  
or ~ 2 kW per NCC

There will be space to provide  
cooling

Each NCC would need ~ 1.5 gpm  
water or ~ 600 cfm air to cool  
the expected load

( based on 5 °C cooling medium  
temperature rise

# Tungsten Quotation

*Quotation from:*  
ATI Firth Sterling,  
Allegheny Technologies:

<u>QTY</u>	<u>Description</u>	<u>Unit Price</u>	<u>Part Subtotal</u>
60	-033 Tungsten plate 17.559"x4.933"x0.358" th	\$1,219.38	\$73,162.80
24	-034 Tungsten plate 12.667"x4.933"x0.358" th	\$1,005.10	\$24,122.40
56	-035 Tungsten plate"x4.933"x0.157" th	\$826.50	\$46,284.00
116	-036 Tungsten plate 17.559"x4.933"x0.157" th	\$1,156.67	\$134,173.72
84	-037	\$925.03	\$77,702.52
48	-038 Tungsten plate 12.667"x4.933"x0.157" th	\$1,020.74	\$48,995.52
			Total \$404,440.96



# Bridge Utilities

Bridge water manifolds and cable trays



Bridge water supply & return flexible connections


Bridge elect. distribution and disconnect



HBD & RXNP Racks. NCC and VTX/FVTX racks will be in these or other racks at ~ these locations

Bridge and utilities efforts will serve all central region detector upgrades

# CM Region Crane and Cable Routing Concept



Cable Trays to route NCC cables from Bridge to Detector

Crane Supports use existing flux return notches

CM Crane north-south & east-west motions; extended travel east to existing crane coverage

Gorbel visit in 11/06; waiting for quote

# NCC Mechanical Efforts

## Current Status

- **General efforts for CM region**
  - Space allocation concept in place
  - CM platform extensions done
  - Crane design underway- waiting for quote -  
Install summer 2007
  - Bridge utilities installed
  - Cable routing in place for HBD/RXNP
- **NCC Specific efforts**
  - Space allocation defined NCC remains ~ within envelope
  - Detector design well established.
  - Structural support concept specified;  
Prototype brick design complete begin fabricating 3/07
  - Installation plan & fixturing need to be finalized
  - Preamp cooling to be designed
  - Cable management to be defined