



FVTX Hardware Commissioning

E.J. Mannel

FVTX Closeout


23-Apr-2012





Chillers

- Uses same chillers as VTX
 - Were installed for RUN-11
 - Manifolds were designed to include FVTX
 - Only required final connections to FVTX
- Based on RUN-11 Experience
 - NOVEC monitored routinely for contaminates
 - Filtering procedure in place to remove contamination







Low Voltage

- Based on PHENIX "Standard" Low Voltage Distribution
 - Separate systems for North/South end caps
 - 196 LV Channels
- Additional control and filtering for wedge LV
 - 768 Wedge channels
- Outside vendors and PHENIX techs produced, tested and installed LV Cables








LV Control

- Software control based on ADAMS interface
 - Common PHENIX slow control
 - Standard GUIs
 - Expert and Shifter versions
 - Provides voltage and current read back







Bias System


- Based on Wiener/ISEG MPOD System
 - Identical system are used by the VTX
 - Additional switching and filtering using FVTX distribution crate. 1 to 8 split
 - Outside vendors and PHENIX Techs assembled, tested and installed Bias cables.
- Software is based on software developed for VTX
- Voltages and currents in database with Web interface







Operator Control







Bias Monitoring








Bias Database Interface

- Current for 8 wedges
- Bias current increasing due to radiation
- Most significant effect from p-p running
- Supply limit 1mA, now at ~30uA







Interlocks


- Fully interlocked on temperature and coolant flow
- Shares same system as VTX
 - Siemens PLC Based
 - 40 Thermal couples for FVTX
 - Disk temperature
 - Big Wheel temperature
- Temperatures and interlock status logged to database







Thermal History







FEM/DCM-2 Crates

- 4 FEM crates w/ 48 FEMs installed in Rack Room
- 1 DCM-2 Crate w/ 6 DCM-2 modules (48 channels)
- All installed and ready for FVTX installation









The Major Players

- Chiller
 - R. Pisani
 - C. Biggs
 - R. Pak
- Low/Bias Voltage
 - F. Toldo
 - S. Boose
 - S. Polizzo
 - P. Giannotti

- Cabling
 - J. LaBounty
 - M. Lenz
 - F. Toldo
- Interlocks
 - P. Giannotti
 - S. Boose.
 - S. Polizzo
 - J. Haggerty
 - M. Lenz





Conclusions

- Chillers are installed and fully operational
- LV system is installed and is fully operational
- Bias system is installed and is fully functional
- Interlock system is installed and is fully operational
- Thanks to the PHENIX Techs whose hard work made it all possible