


---

# FVTX Project Overview Cost & Schedule

Melynda Brooks



Los Alamos National Laboratory


FVTX Project Manager



# Talk Outline

- Project Overview
- Addressing past Review Questions
- Construction Progress
- FY11 Technical Plans
- Budget and Schedule Summary
- Day's agenda






# Why an FVTX Detector for Muons?



## Enhance Muon performance to allow precision heavy flavor measurements


- Initial absorber to reduce hadrons that reach the active detectors
- Muon Tracking stations inside magnet to find tracks and measure momentum
- Muon Identifier for  $\mu/\pi$  separation, Lvl-1 trigger
- ~1% “punch through”, ~1% decay into muon before absorber, ~1%\*15% decay after the absorber
- No way to discriminate  $\pi/K \rightarrow \mu$ ,  $D/B \rightarrow \mu$ ,  $\pi/K$  punch-through
- Mass resolution limited by absorber
- Track isolation information lost by absorber

$$\eta = 1.2$$



$$\eta = 2.4$$





# Physics Programs Accessible With FVTX

## Single Muons:

- Precision heavy flavor and hadron measurements at forward rapidity
- Separation of charm and beauty
- W background rejection improved


## Dimuons:

- First direct bottom measurement via  $B \rightarrow J/\psi$
- Separation of  $J/\psi$  from  $\psi'$  with improved resolution and S:B
- First Drell-Yan measurements from RHIC
- Direct measurement of c-cbar events via  $\mu^+\mu^-$  becomes possible

## Physics:

- Advance understanding of energy loss, by adding precise heavy flavor measurements of  $R_{AA}$  and flow.
- First detection of  $\psi'$  plus heavy quark allow detailed understanding of vector meson production and modification
- Separation/Understanding of Cold Nuclear Matter and QGP effects with rapidity coverage
- Precise gluon polarization and sea quark measurements over large x range, fundamental tests of Sivers functions possible








# FVTX Geometrical Design


## Four tracking stations with full azimuthal coverage

- 75  $\mu\text{m}$  pitch strips in radial direction, 3.75° staggered phi strips
- Radiation length < 2.4%/wedge to minimize multiple scattering
- Outer Support and Cooling outside active area
- Kapton cable plant primarily outside active area







# FVTX Electrical Design

- p on n ministrip sensor,  $75\ \mu\text{m} \times 3.75^\circ \rightarrow$
- Data push FPHX readout chip  $\rightarrow$
- High density interconnect cable  $\rightarrow$
- ROC (big wheel area in IR)  $\rightarrow$
- FEM (VME crate in counting house)  $\rightarrow$
- PHENIX DCMs



FEM, IB, Counting House


ROC, IR



PHENIX


Melynda Brooks, FVTX Annual Review, November 2010





---

# FY09 Recommendations



## 2009 Annual Review Recommendations

*"A technical line of communication regarding the HDI manufacture should be established with Dyconex immediately. This communication would best be initiated in person at their facility."*


### Reminder of November 2009 Status (last year's review):

- All prototype HDIs tested good, but poor communication from manufacturer to FVTX group about handling of bubbling during processing (holes were introduced into the design)
- HDI driving wedge assembly which was on the critical path so delivery of working HDIs very important to the Project's schedule

### Response:

- Jon Kapustinsky, Eric Mannel traveled to Dyconex (Switzerland), MSE (Germany) shortly after review
- Met with management and technical personnel, gave presentation on project, took tour of facilities
- Maintained close communication with Dyconex/MSE staff as well as technical representative that we used previously throughout HDI production





## 2009 Annual Review Recommendations

*"The FVTX team should actively plan for the production cycle of the Wedges by identifying risks and implementing mitigating strategies that could increase the probability of having the Wedges produced on schedule. "*


### Reminder of November 2009 Status (last year's review):

- Wedge assembly on the critical path

### Response:

- Submitted HDI PR with hand-carry (fastest) schedule. Unfortunately, time lost in lawyer's negotiations, but got hand-carry process once started.
- Active participation with SiDet to optimize wedge assembly (See Dave Winter's talk)
- Prompt testing of all components made all but HDIs available in advance of beginning of wedge assembly.
- Result – wedge assembly met project schedule until delay of last HDI delivery (see later). May still be completed on time.

WBS Number	Control Milestone Name	Baseline Date
WBS 1.1	DOE construction funds received	Q3 FY08
Accounts open	Accounts open	Q3 FY08
WBS 1.6.2.2.2	Review and Approve wedge, disk, cage design	Q3 FY08
WBS 1.4.3.2.5	HDI tested	Q3 FY08
WBS 1.4.1.2.3	Sensor prototype tested	Q1 FY09
WBS 1.4.1.2.5	First prototype wedge assembly	Q1 FY09
WBS 1.5.2.2.6	PHENIX system test complete	Q1 FY09
WBS 1.5.2.2.8	Review and Approve FEM and ROC	Q2 FY09
<b>WBS 1.4.3.3.1</b>	<b>1<sup>st</sup> Production HDIs Received</b>	<b>Q2 FY10</b>
WBS 1.4.1.3.1	Sensor Procurement complete	Q3 FY09
WBS 1.4.1.2.6	Wedge assembly test complete	Q4 FY09
WBS 1.4.2.5.1	FPHX engineering run complete	Q1 FY10
WBS 1. 5.3	ROC and FEM production Complete	Q2 FY10
<b>WBS 1.7.1.1</b>	<b>Disk Assembly begins</b>	<b>Q3 FY10</b>
<b>WBS 1.7.2.1</b>	<b>First Two ½ Cages Assembled</b>	<b>Q1 FY11</b>
<b>WBS 1.7.2.1</b>	<b>Functional Requirements Tests on Bench Begins</b>	<b>Q1 FY11</b>
WBS 1.5.5.6	Install ancillary Equipment	Q4 FY10
<b>WBS 1.7.1.1</b>	<b>Disk Assembly complete</b>	<b>Q1 FY11</b>
WBS 1.7.2.1	½ Cage Assembly finished	Q2 FY11
	<b>All FVTX Component Deliverables Completed</b>	<b>Q2 FY11</b>
<b>WBS 1.7.5</b>	<b>Verify Functional Requirements on Bench Completed</b>	<b>Q3 FY11</b>
<b>WBS 1.7.3</b>	<b>Install into VTX enclosure</b>	<b>Q4 FY11</b>
<b>WBS 1.7.3</b>	<b>Project Complete</b>	<b>Q4 FY11</b>



## 2009 Annual Review Recommendations

---

*"The FVTX team should present a detailed commissioning plan, including necessary scientific and technical personnel, at the next (2010) annual review. "*

### Response:


- Commissioning topics covered throughout the day and in the Commissioning Talk

*"PHENIX and the FVTX team should develop and present, at the next annual review, a plan to experimentally estimate the DCA background distributions and to tune their simulations accordingly. The necessary personnel to carry out these studies with the Run 12 data should also be identified. "*

### Response:

- We can select/enhance contribution from real data prompt particles, punch-through hadrons, decay hadrons by cutting on J/psi events, Muon Identifier momentum for stopped particles in the Muon Identifier, and compare DCA distributions from these selected events to Monte Carlo distributions.
- See Software Talk





---

# Technical Progress

# FY10 Progress - Technical

## Wedge Components

- All sensors procured and tested. ~100% yield
- 24 FPHX wafers procured and 17 tested, >95% yield
- All small HDIs received (125), 25 large HDIs received, rest in progress, ~100% yield
- All backplanes received and within specifications

## Detector Assembly






- 120(118) small production wedges with chips (chips+sensors) and 23 large production wedges assembled at SiDet
- Disk assembly at BNL underway, cage assembly plan in place


## DAQ

- FEM Interface 1<sup>st</sup> article tested good, rest in assembly
- FEM production board 1<sup>st</sup> article received and tests good
- Full ROC prototype underway.

## Mechanics

- Disk, cage fabrication in progress
- Assembly fixtures for disk, cage completed






# FY10 Project Hurdles

## Schedule Issues and Mitigation Strategies

- **~3 month delay in Initial HDI Delivery:** HDI PR submitted in November 2009 with anticipated delivery by January/February. Lawyer negotiations did not accept terms of PR until ~March 2010, delivery of HDIs in May 2010.
- Active work with SiDet to optimize wedge assembly plus project contingency → assembly rate was making up most of the 3 month delay (until delay of last HDI delivery)
- **Delay of last batch of HDIs** → 150 HDIs delivered and working well, then last large HDI batch failed in manufacturing process. Rapid succession of technical discussions to determine best path forward, Follow-up with in-person visit to Dyconex. Large HDIs that were to have been delivered in October will be delivered in December and January. SiDet can ~double manpower for wedge assembly. Large disk assemblies will have to be compressed, full cage assembly delayed.
- **Mechanical Disk Delay** – Engineering company dissolved by new parent company unexpectedly in Dec. 2009 → had to bring on designers/engineer as contractors. Iteration on design to reduce price, Slow PR process → October delivery of first disk.





# FY10 Project Hurdles


---

## Schedule Issues (cont'd)

- **ROC delay** – Layout has taken much longer than anticipated (designer availability + design work more complicated than anticipated). LANL management negotiated with designer groups to have all resources applied to layout work. Some cost coverage by LANL. Assembly will use already available boards for testing until final round ROC boards become available. (more details in schedule discussion)

## Technical

- Prototyping/production on many fronts at once this past year – sensors, FPHX chips, backplanes, HDIs, FEM cards, FEM Interface cards ROC cards, disk, cage, assembly fixtures.
- Employed multiple checks on electrical and mechanical designs.
- Overall, no major technical flaws found in production designs.



# FY11 Technical Work

## Wedge, Disk and Cage Assembly

- Wedge assembly at SiDet
- Disk Assembly at BNL
- Cage Assembly at BNL

## DAQ


- Production FEM Interface and FEM boards in hand or in assembly line
- ROC prototype board should be received November/December 2010
- Full ROC production January 2011 (?)


## Bench Testing and Commissioning

- Disk Testing during assembly
- Individual Cage Testing during assembly
- Multiple Cages with FVTX on Bench
- FVTX and VTX installed into IR
- Functional Testing in IR

## IR Preparation

- Installation of power, cabling, etc.






## Project Reviews

Feb-April 2008  
August 2008  
August 2008

FPHX Design Reviews before prototype submission  
Overall Electronics Design Review  
Informal Mechanics Review of Components

May 2009  
June 2009  
Sep 2009  
Oct 2009


FPHX review prior to FPHX-2 prototype  
1<sup>st</sup> RHIC Safety Review  
FPHX review prior to production  
HDI review prior to 2<sup>nd</sup> prototype




Dec 2009  
June 2010  
Dec 2010  
Late 2011

Final HDI and Interconnect Cable review  
Go-Ahead for FEM/FEM Interface Production  
ROC final review  
PHENIX Readiness Review

Note: each FPHX review was presented as a “system” review already




ROC



FEM






# FVTX Project Deliverables

Item	Number	Working Spares
Wedge assemblies		
Large Sensors	288	25 in spare wedges
Small Sensors	96	8 in spare wedges
Large Wedges	288	25
Small Wedges	96	8
ROC boards	24	4
FEM boards	48	6
Mechanical		
Large ½ Disks	12	2
Small ½ Disks	4	1
Suspension system	1 (VTX funded)	0
Dry gas enclosure	1 (VTX funded)	0
Cooling system	1 (VTX funded)	0
Power supply system	1	Spare components available
DCM channels	48	4


KEY:  
 Done  
 In Progress



## FVTX Functional Requirements

Mini strips active	>80%	(expect ~99%)
Hit efficiency	>85%	(expect ~99%)
Radiation length per wedge	< 2.4 %	
Detector hit resolution	< 25 $\mu\text{m}$	(can achieve without analog information)
Random noise hits/chip	<0.1%	(threshold:noise ~5:1)
Level-1 latency	4 $\mu\text{s}$	
Level-1 Multi-Event buffer depth	4 events	
Read-out time	< 40 $\mu\text{s}$	
Read-out rate	> 10 kHz	


\*Primary bench test requirements. Others are met by design



---

# Cost & Schedule






## FY10 Project Hurdles

---

### Costs – significant increase in few project costs have reduced contingency

- \$172k more for mechanical components (backplane, disk, cage)
- \$506k more for HDI + extension cables (“fast” HDI delivery + significant extension cable NRE \* 16 types)
- ~\$100k more for Ancillary Systems (power distribution, DCMs)
- Mitigation – had to take above increased costs, but worked to keep other costs from increasing:
  - Negotiated somewhat lower price for extension cables
  - Redesign work with LBNL to bring initial disk estimate down to 2.5\* lower than initial quote
  - Negotiations at LANL resulted in LANL covering part of extra ROC design costs
  - Did not accept ~\$50k over-charge from contracted institution that carried out work beyond scope
  - Continue to look for cost reductions wherever we can.



## Cost Summary


---

### FVTX Cost Roll-Up:

- Management Plan Cost = \$4880k, Contingency = \$927k (23%)
- \$4276k costs and commitments to date
- Remaining Cost to Complete = \$523k with Contingency = \$101k (19%)

### Primary Remaining Costs

ROC production board (but many parts already procured) - ~\$275k remaining  
Remaining FEM production boards – PR in place, just need to give go-ahead - \$99k  
Engineering Support - \$55k  
Power Distribution boards - ~\$40k  
Endcap assembly - \$30k



## Schedule Summary


---

Current Schedule: Project Deliverables June 30 2011, Sept. 30 2011


- |                                       |                            |
|---------------------------------------|----------------------------|
| • Wedge Assembly                      | Jun 2010 – Feb 2011        |
| • Disk Assembly                       | Nov 2010 – May 2011        |
| • Disks into Cages                    | Feb 2011 – Jun 2011        |
| • <b>Test Functional Requirements</b> | <b>Mar 2010 – Jun 2011</b> |
| • Schedule Float                      | 6/7/11 – 6/30/11           |
| • Install and Test in IR              | Jul 2011 – Sept 2011       |
| • <b>Project Complete</b>             | <b>September 30, 2011</b>  |

- Options to increase schedule float:
  - **Parallel assembly of disks (done serially now):** wedge preparations finished in March, last disk does not get assembled until May so 1-2 months could be gained here if infrastructure is in place
  - **Earlier delivery of 1<sup>st</sup> large wedges:** Steve assumes large wedges not available until 1/31, but could be ready sooner

# FVTX Project File




24




- ◆Wedge assembly still near critical path
- ◆However, End date (2/4) not so far from 1/13 from last year



# FVTX Project File




25




♦ Extension cables ~Jan.

♦ ROC: Jan-Feb


# FVTX Project File




26




# FVTX Project File



27






# FVTX Project File

ID	WBS	Task Name	Start	Finish												
					2010				2011				2012			
					2nd Half		1st Half		2nd Half		1st Half		2nd Half		1st Half	
					Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1
165	1.7.2.4	Schedule Contingency	Mon 6/6/11	Thu 6/30/11												
166	<b>1.7.10</b>	<b>Install cages into VTX enclosure</b>	<b>Fri 7/1/11</b>	<b>Fri 9/30/11</b>												
167	1.7.10.10	RHIC Shutdown begins	Fri 7/1/11	Fri 7/1/11												
168	1.7.10.6	Prepare Enclosure for FVTX Installation	Tue 7/5/11	Mon 8/1/11												
169	1.7.10.1	Install 2 half cages into enclosure	Tue 8/2/11	Mon 8/8/11												
170	1.7.10.7	Survey half cages in enclosure	Tue 8/9/11	Mon 8/15/11												
171	1.7.10.8	Reinstall enclosure in IR	Tue 8/16/11	Mon 8/22/11												
172	1.7.10.9	Survey VTX and FVTX in IR	Tue 8/23/11	Mon 8/29/11												
173	1.7.10.2	Connect to infrastructure and test	Tue 8/30/11	Fri 9/30/11												
174	1.7.10.11	Project Complete	Fri 9/30/11	Fri 9/30/11												
175	<b>1.8</b>	<b>System Integration</b>	<b>Wed 4/2/08</b>	<b>Wed 8/24/11</b>												
176	1.8.1	Mechanical engineer	Wed 4/2/08	Wed 8/24/11												
177	1.8.2	Electrical Engineer	Wed 4/2/08	Wed 8/24/11												
178	1.11	<b>FVTX Management</b>	Wed 4/2/08	Wed 8/24/11												

## ♦ Installation into IR






## ARRA FVTX Funds, Milestones

\$2M in ARRA funds received in summer 2009. Milestones:


	Plan	Actual
Initiate Backplane procurement process	6/2009	6/2009
Initiate Cage procurement process	6/2009	6/2009
Start Recovery Act FVTX Management and Integration by LANL	7/2009	7/2009
Initiate Ancillary System procurement process	11/2009	11/2009
Review and approve ROC/FEM design	12/2009	12/2010
Initiate ROC/FEM production procurement process	1/2010	3/2010
Begin testing ROC/FEM board	2/2010	9/2010
Begin attaching HDIs to Backplane	3/2010	5/2010
Begin testing production version of FPHX chips	4/2010	4/2010
Begin attaching chips to HDIs	6/2010	6/2010
Begin attaching sensors to HDIs	7/2010	6/2010
Begin testing wedge assemblies	8/2010	6/2010
Begin assembling wedges into disks	9/2010	11/2010



WBS Number	Control Milestone Name	Baseline Date	Actual/ Forecast Date
WBS 1.1	DOE construction funds received	Q3 FY08	Q3 FY08
Accounts open	Accounts open	Q3 FY08	Q3 FY08
WBS 1.6.2.2.2	Review and Approve wedge, disk, cage design	Q3 FY08	Q3 FY08
WBS 1.4.3.2.5	HDI tested	Q3 FY08	Q2 FY09
WBS 1.4.1.2.3	Sensor prototype tested	Q1 FY09	Q1 FY09
WBS 1.4.1.2.5	First prototype wedge assembly	Q1 FY09	Q2 FY09
WBS 1.5.2.2.6	PHENIX system test complete	Q1 FY09	Q3 FY09
WBS 1.5.2.2.8	Review and Approve FEM and ROC	Q2 FY09	Q1 FY11
WBS 1.4.3.3.1	1 <sup>st</sup> Production HDIs Received	Q2 FY10	Q3 FY10
WBS 1.4.1.3.1	Sensor Procurement complete	Q3 FY09	Q3 FY10
WBS 1.4.1.2.6	Wedge assembly test complete	Q4 FY09	Q4 FY09
WBS 1.4.2.5.1	FPHX engineering run complete	Q1 FY10	Q1 FY10
WBS 1. 5.3	ROC and FEM production Complete	Q2 FY10	Q2 FY11
WBS 1.7.1.1	Disk Assembly begins	Q3 FY10	Q1 FY11
WBS 1.7.2.1	First Two ½ Cages Assembled	Q1 FY11	Q2 FY11
WBS 1.7.2.1	Functional Requirements Tests on Bench Begins	Q1 FY11	Q1 FY11
WBS 1.5.5.6	Install ancillary Equipment	Q4 FY10	Q2 FY11
WBS 1.7.1.1	Disk Assembly complete	Q1 FY11	Q2 FY11
WBS 1.7.2.1	½ Cage Assembly finished	Q2 FY11	Q3 FY11
	All FVTX Component Deliverables Completed	Q2 FY11	Q3 FY11
WBS 1.7.5	Verify Functional Requirements on Bench Completed	Q3 FY11	Q3 FY11
WBS 1.7.3	Install into VTX enclosure	Q2 FY11	Q4 FY11
WBS 1.7.3	Project Complete	Q3 FY11	Q4 FY11

FVTX Cost Estimate		TPC	Baseline Cost	Baseline	Remaining	Cost
2 endcaps		2007	with	contingency	contingency	AY\$
Mechanics			contingency			
WBS			AY			
	1.6					
Cage	1.6.2	352	174	35	-108	282
Backplane	1.6.3		188	38	24	164
Disk	1.6.4		114	23	-95	208
Alignment and Assembly jigs	1.6.5.2	60	80	15	18	62
	1.6 totals	412	555	110	-161	716
Sensor						
Silicon Sensor	1.4.1					
prototype sensor and test	1.4.1.2	85	107	19	-33	140
purchase	1.4.1.3	410	553	107	128	425
sensor Q/A and testing	1.4.1.3.2	50	62	8	55	7
attach HDI to backplane	1.4.1.3.3	30	39	7	30	9
attach sensor	1.4.1.3.4	30	39	7	30	9
wire bond assembly	1.4.1.3.5	188	263	49	55	208
test wedge assembly	1.4.1.3.6	40	54	9	10	45
Sidet prototype assembly	1.4.1.1		0		-19	19
	1.4.1 totals	833	1118	206	256	863
FPHX						
	1.4.2					
1 st Prototype	1.4.2.4.1	0	0	0	-45	45
2 nd + 3rd Mosis run and test	1.4.2.4.4	175	242	51	92	150
FNAL coding	1.4.2.4.9	0	0	0	-37	37
FPHX test stands	1.4.2.4.9		0		0	0
engineering run	1.4.2.5.1	240	385	115	128	258
testing	1.4.2.5.2	50	64	8	13	52
	1.4.2 totals	465	692	174	150	542


FVTX Cost Estimate		TPC	Baseline Cost	Baseline	Remaining	Cost
		2007	with contingency	contingency	contingency	AY\$
<b>2 endcaps</b>	<b>WBS</b>					
HDI bus	1.4.3	143	194	39	-235	429
flex cables, sensor to ROC	1.4.4	56	70	9	-329	398
	<b>totals</b>	<b>1497</b>	<b>2074</b>	<b>428</b>	<b>-158</b>	<b>2232</b>
<b>Readout Electronics</b>						
ROC electronics	1.5.2					
preproduction proto	1.5.5.2	71	100	26	-168	268
Clock and Interface		0	0	0	-41	41
production	1.5.5.3.1	337	497	111	123	374
Q/A	1.5.5.3.2	14	18	2	18	0
	<b>totals</b>	<b>422</b>	<b>615</b>	<b>139</b>	<b>-68</b>	<b>683</b>
FEM electronics	1.5.3					
preproduction	1.5.3.2	80	116	29	-39	155
production	1.5.3.3.1	301	444	99	239	205
Q/A	1.5.3.3.2	14	18	2	18	0
fibercables, ROC-FEM	1.5.1	17	21	3	2	19
lab equipment	1.5.5.5	100	117	10	91	26
	<b>totals</b>	<b>512</b>	<b>716</b>	<b>143</b>	<b>312</b>	<b>405</b>
<b>Ancillary Systems</b>						
	1.5.5					
Racks, LV, HV, DCM, crates, install	1.5.5.1-1.5.5.6	99	123	12	-99	222
slow controls	1.5.5.4	5	7	1	7	0
calibration system	1.5.4					0
	<b>totals</b>	<b>104</b>	<b>130</b>	<b>13</b>	<b>-92</b>	<b>222</b>



# FVTX Cost Estimate

<b>Assembly</b>						
Assemble endcap	1.7	30	42	8	19	23
<b>Integration</b>						
Electronics Integration	1.8.2	165	189	23	92	97
Mechanical Integration	1.8.1	250	311	35	80	231
<b>totals</b>		<b>415</b>	<b>500</b>	<b>58</b>	<b>172</b>	<b>327</b>
<b>Management</b>						
Management	1.9	200	249	28	77	172
<b>total</b>		<b>3593</b>	<b>4881</b>	<b>927</b>	<b>101</b>	<b>4780</b>





## Issues/Concerns

---

### Maintaining cost & schedule through remainder of project


- Major components are committed/quoted, but still need to watch for unexpected additional costs
- Continual assembly effort required for several months to reach project complete

### Maintaining performance through full system tests

- Careful system testing at each stage important for optimizing power + grounding, maintaining performance

### Time to install detector into IR for final project deliverable

- Time between IR access and project complete is expected to be short
- Very careful planning required to meet schedule.
- VTX installation this year means much of the infrastructure will already be in place, and PHENIX will already have significant experience in preparing and installing enclosure into the IR



## Summary

Production of almost all major detector components during last year:

- No major technical issues uncovered in performance tests, high yields


Project Schedule took a few hits:

- Some delays already absorbed by efficient testing of components, high yields, and faster wedge assembly than FY09 Project File
- 8 months to assemble disks and cages still looks like sufficient time to complete project
- IR assembly will still be challenging

Project Cost Contingency Reduced:

- Careful management of remaining funds needed






## Day's Agenda


---

10:00 - 10:20	Sensors/FPHX Readout Chip (WBS 1.4.1, 1.4.2)	Jon Kapustinsky
10:20 - 10:40	Break	
10:40 - 11:10	High Density Interconnect and Extension (WBS 1.4.3, 1.4.4)	Doug Fields
11:10 - 11:40	Wedge Assembly (WBS 1.4.1.3.3 – 1.4.1.3.9)	Dave Winter
12:00 - 1:00	Lunch	
1:00 - 1:15	Mechanics (WBS 1.6)	Walt Sondheim
1:15 - 1:55	Detector Assembly (WBS 1.7)	Steve Pate
1:55 - 2:10	Mechanical Integration (WBS 1.6)	Robert Pak
2:10 - 2:50	DAQ Overview (WBS 1.5.2, 1.5.3)	Sergey Butsyk
2:50 - 3:10	Break	
3:10 - 3:40	Electrical Integration (1.8.2)	Eric Mannel
3:40 - 4:10	Physics Simulation Results	Zhengyun You
4:10 - 4:40	Commissioning (ppt)	Jon Kapustinsky



---




# Backups




# Reminder of Simulated Performance

Improved S:B in heavy flavor via single muons allows precision heavy flavor  $R_{AA}$ ,  $A_{LL}$  measurements

(Updated Information in Simulation Talk)







## Cost Updates Since Last Year


### Included In Current Costs:

FEM Production	\$ 95k savings
ROC Prototype + Production	\$109k additional cost
Increased Mechanical Costs	\$172k additional cost
Ancillary systems (Power Dist, DCMs)	\$106k additional cost
Extension Cable	\$336k additional cost
Production HDI	\$170k additional cost

Management Plan Cost = \$4880k, Contingency = \$927k  
 \$4276k costs and commitments to date and remaining Contingency = \$101k (19%)


### Primary Remaining Costs

ROC production board (but many parts already procured) - ~\$200k remaining  
 Power Distribution boards - ~\$40k  
 Endcap assembly - \$30k



## Management Plan Milestones

<b>WBS 1.1 DOE construction funds received</b>	<b>Q3 FY08</b>
<b>WBS 1.6.2.2.2 Review and approve wedge, disk, cage design</b>	<b>Q3 FY08</b>
<b>WBS 1.4.3.2.5 HDI tested</b>	<b>Q3 FY08</b>
<b>WBS 1.4.1.2.3 Sensor prototype tested</b>	<b>Q1 FY09</b>
<b>WBS 1.4.1.2.5 First prototype wedge assembly complete</b>	<b>Q1 FY09</b>
<b>WBS 1.5.2.2.6 PHENIX system test complete</b>	<b>Q1 FY09</b>
<b>WBS 1.5.2.2.8 Review and approve FEM and ROC</b>	<b>Q3 FY09</b>
<b>WBS 1.4.1.3.1 Sensor Procurement complete</b>	<b>Q3 FY09</b>
<b>WBS 1.4.1.2.6 Wedge assembly test complete</b>	<b>Q4 FY09</b>
<b>WBS 1.4.2.5.1 FPHX engineering run complete</b>	<b>Q1 FY10</b>
<b>WBS 1. 5.3 ROC and FEM production complete</b>	<b>Q2 FY10</b>
<b>WBS 1.7.1 Start endcap assembly</b>	<b>Q3 FY10</b>
<b>WBS 1.5.5.6 Ancillary electronics installed</b>	<b>Q4 FY10</b>
<b>WBS 1.7.2 Start installation into cage enclosure</b>	<b>Q4 FY10</b>
<b>WBS 1.7.1.1 Place wedges on cooling plate complete</b>	<b>Q1 FY11</b>
<b>WBS 1.7.2.1 ½ Cage assembly complete</b>	<b>Q2 FY11</b>
<b>WBS 1.7.3 Install cages into VTX enclosure complete</b>	<b>Q2 FY11</b>
<b>WBS 1.7.5 Verify functional requirements and Project Complete</b>	<b>Q3 FY11</b>



# Organizational Chart

