

# Report from MVTX Workfest at MIT

Ming Liu  
Los Alamos

# MVTX-HF Workfest @MIT 4/30-5/1

- Primary goals: discuss and refine a roadmap for MVTX realization
  - ~20 people attended, MVTX, INTT experts and sPHENIX management and project offices;
  - defined near term action items for MVTX/INTT integration in sPHENIX
  - A mini-sPHENIX integration review proposed, ~last week of June
- Monday April 30:
  - a series of presentations & discussions of current considerations on budget & schedule and possible cost reduction measures, and MVTX+INTT integration
- Tuesday May 1:
  - mostly follow up on day-1 discussions, near term R&D, MVTX + INTT

Workfest indico page: <https://indico.bnl.gov/event/4380/>

# Topics discussed

News from sPHENIX workshop in China;

Involvement in MVTX project from Chinese Consortium;

- 1) stave production, test and simulations;
- 2) possible joint R&D and/or production of carbon structures

MVTX project status and plan:

- Working on early procurement of Readout Units and Staves from ALICE/CERN, EIC R&D proposal to DOE
- Highlight from Fermilab test beam
- MVTX integration in sPHENIX
- Project schedule and funding profile smoothing to fit projected sPHENIX cash flow
- Near term R&D for MVTX and INTT
- New development in physics and simulations

ALD asked to have a mini-review of sPHENIX tracking integration ASAP (MVTX+INTT+TPC + ...)

- the week of June 25<sup>th</sup> or early July, TBD
- Carry out critical integration R&D MVTX, INTT..

A joint MVTX+INTT test beam at Fermilab, Jan-Feb 2019

- Full subsystem test
- INTT ~1.2m extension bus
- MVTX, full staves with possibly extended FPC

	Welcome and Goals of the Workfest	Gunther Roland
	Room 24-507, MIT	08:45 - 09:00
09:00	Report from sPHENIX Workshop in China	David Morrison
	Room 24-507, MIT	09:00 - 09:30
	MVTX Project Status	Grazyna Odyniec et al.
10:00	Room 24-507, MIT	09:30 - 10:30
	Coffee break	
	Room 24-507, MIT	10:30 - 11:00
11:00	Physics impact of MVTX & new Development	Xin Dong
	Room 24-507, MIT	11:00 - 11:30
	MVTX Project Schedule and Funding Profile	David Lee
	Room 24-507, MIT	11:30 - 12:00
12:00	sPHENIX system integration: MVTX+INTT+TPC Mechanics	Mickey Chiu et al.
	Room 24-507, MIT	12:00 - 12:30
	Near Term INTT R&D	Rachid Nouicer
	Room 24-507, MIT	12:30 - 13:00
	Room 24-507, MIT	13:00 - 14:00
14:00	sPHENIX system integration: MVTX+INTT+TPC Electrical	Eric Mannel
	Room 24-507, MIT	14:00 - 14:30
	Near Term MVTX R&D	Ming Liu et al.
	Room 24-507, MIT	14:30 - 15:00
15:00	Near Term Simulations and tracking development	Haiwang Yu
	Room 24-507, MIT	15:00 - 15:30

# A Broad Physics Program

Xin & Jin

Total bottom cross section

Upsilon suppression in heavy-ion collisions

Hadronization


Charm baryon  $\Lambda_c$  production

Initial magnetic field

Directed flow of D and Dbar mesons


Gluon distributions in nucleons/nuclei at EIC

Charm Directed Flow – Direct Access to Initial B Field



MVX or MVX+ for EIC ?


- Kinematic coverage
- Mechanical support/service
  - integration effort with forward/backward tracking detectors
- Radiation damage concern?
- Readout speed / trigger (?)



Apr. 30<sup>th</sup> - May 1<sup>st</sup>, 2018

MVX Workfest, MIT

14



# Simulations

## sPHENIX tracking software

### What we have:


- Laddered G4 models for MVTX and INTT
- Improved and improving clustering alg. for TPC, INTT and MVTX
- Kalman Filter track following pattern recognition
  - Configurable iterations
- GenFit based final track fitting
- RAVE based 3D multi-vertexing
- Track projection tools
- Fast tracking tools
- etc.

### New update:

- TPC zig-zag readout simulation
- Optimization of seed fitting and iterative strategies for PatRec
- Standalone initial Z-vertexing module

### Working on:

- Integrating the initial vertexing to the main track reco. chain
- Improving TPC clustering under high occupancy
- Code reorganization for long term development
- New PatRec alg.



4/30/18

Haiwang for MVTX Workfest

2


## More sophisticated algorithm?

### More sophisticated algorithm

- Using all DCA information comprehensively
- Using more features to help
- Need to output one curve


### First try with Random Forest

- [https://www.stat.berkeley.edu/~breiman/RandomForests/cc\\_home.htm#overview](https://www.stat.berkeley.edu/~breiman/RandomForests/cc_home.htm#overview)
- At each split, 'mtry' features randomly chosen, use the one with best Gini gain



4/30/18

Haiwang for MVTX Workfest



13

## As part of a EIC detector prototype

### Vertexing info. used in sPHENIX LOI last year:

- [https://www.sphenix.bnl.gov/web/system/files/sPH-cQCD-2017-001\\_draft\\_2017\\_06\\_02.pdf](https://www.sphenix.bnl.gov/web/system/files/sPH-cQCD-2017-001_draft_2017_06_02.pdf)

### Available to simulate MVTX as part of a EIC detector

- G4 models of staves
- Fast tracking


### Missing:

- Material for (possibly redesigned) forward support structure
- Manpower in carrying out studies

### Suggestions welcomed

### G4 event display - ePHENIX - J. Huang



<https://indico.bnl.gov/event/4464/>



4/30/18

Haiwang for MVTX Workfest

### fsPHENIX



14

# RU Production Plan

## Plan-A

- To be part of ALICE ITS production
- Timeline:
  - Production starts ~May 2018, available by ~end of 2018, fully tested
- Need to make commitment “NOW”
  - BNL management actively working on funding RU through RHIC \$

## Plan-B

- Produce RU later, ~2019 as funding allows?
  - Procure GBT chips from CERN
  - Production & test in US, UT-Austin, LANL et al.
- Higher cost, 2x
- Higher technical and schedule risks

# Stave Production Plan

## Plan-A

- Produce staves following the completion of ALICE IB at CERN, using ALICE facility
- Timeline:
  - Starting as early as Aug/Sep 2018 +, last about 6 months for production and test
- All 84 staves produced and tested at CERN
- BNL management actively working with DOE to build staves at CERN

## Plan –B


- Produce full staves at CCNU later as funding allows, ~2019?
- Earliest starting date - May 2019 + , ~12 months (could be shorter)
- Higher technical and schedule risks
- Impact on cost, TBD

# Carbon Structure Design and Fabrication

- Mechanical system design
  - MIT + LANL + LBNL + BNL
- Production
  - LBNL
- Alternative path for fabrication being explored
  - Europe (France & Italy, used for ITS Upgrade)
  - Asia (Korea, China)



# Current Profile (Cost): Funding Profile Smoothing, FY20-22




FY2018	FY2019	FY20	FY21	FY22
1449	1645	1223	364	46

# MVTX Test Beam at Fermilab

## 02/20-03/10, 2018

- Goals:
  - Test full readout chain
  - Evaluate ALPIDE sensor performance
- Experimental setup
  - A 4-sensor telescope
  - Full readout chain: MAPS+RU+FELIX+RCDAQ
    - Parasitic with INTT run
    - Very productive & collaborative


→  
120 GeV  
proton






# Fermilab Test Beam Setup 03/2018

4-ALPIDE Telescope + 4-SamTec cables + 1 RU + 1 FELIX("CRU")

Amazing work by Sho, Alex et al



# Fermilab Test Beam Results (I)




Beautiful analysis done by Sanghoon and Darren et al

# Fermilab Test Beam Results (II)


Hit Spatial Resolution:  $< 5 \text{ um}$

Run 114 -- L0 -- dz




Hit Efficiency  $> 99.5\%$

Run 114



# INTT Integration

Rachid




Latest design of INTT support from Dan Cacace



# MVTX/INTT Integration Review: ~last week of June (TBD)

- w/ ~50cm FPC power extension
  - @LANL, voltage drop, noise pickup
  - MVTX conical structure modification, reduced radius
- w/ 10cm extension FPC – Plan A
  - INTT layout, “cables” and supporting structures
  - Final extension bus ~1.2m, INTT, summer 18
  - MVTX conical structure modification
  - 10cm HS signal simulation now ..
  - Early R&D possible? right now, ~Sept 2018 @CERN
  - Mechanical mockup: MVTX+INTT + .. , @BNL, LANL
- w/o FPC extension – Plan B
  - Revisit INTT layout, cables and supporting structures
  - Final 1.2m bus, summer 18
  - MVTX conical structure modification
- INTT/MVTX simulations
  - New INTT postdoc, INTT optimization, including supporting str
- Resources
  - MIT engineers Jim/Jason ?
  - Walt, Dan, Mike L, Hubert, Chris ...,
  - new \$\$ from non-MIE BNL project? New engineers? Under discussion

## INTT-MVTX Space Conflict



- Currently a clear conflict between the INTT and MVTX
  - INTT only includes ladder, no connectors, cooling barbs, etc


### R&D items:

- 1) Extend cables to move the conical structure further out in z-direction;
- 2) Design/optimize INTT layers to fit current MVTX geometry;
  - FPC data cable can't be easily extended (max additional ~10cm, machine limit)
  - Reduce angle of cone – redesign C-structures and connectors

5/1/18

MVTX/HF Workfest @MIT

47









# MVTX Flexible Printed Circuit (FPC)

Extend MVTX Service Cables?

Maximum +10cm for HS signal, TBD through R&D



# Work in Progress

Mickey, Dan, Walt, Rachid et al

