


MVTX Overview

Ming Liu

Pre-QM sPHENIX Collaboration Meeting

November 1-2, 2019

Fudan Univ., China





A Monolithic Active Pixel Sensor
Detector for the sPHENIX
Experiment

MVTX Detector

Service cone: signal, power, cooling
and mechanical support

CYSS: Cylindrical Shell Structure



MVTX
parameters

	R_min (mm)
Layer 0	24.61
Layer 1	31.98
Layer 2	39.93

3-layer sensor barrel
- 48 staves, 27.1cm long
- 432 chips

Scope of the MVTX Project – WBS 3.02

- Mechanical system (3.02.03, 3.02.04)
 - MVTX detector mechanical structures
 - Design & simulations
 - End Wheels
 - Cylindrical support structure
 - Service barrels
 - Mechanical system integration
 - Service barrel support & interface to sPHENIX
 - Installation tooling etc.
 - Adopt ALICE cooling parameters
 - Detector safety
 - Detector assembly
 - Stave QA & detector assembly @LBNL
- Electronics (3.02.02)
 - Readout Integration
 - RU QA & assembly @UT-A
 - Backend: ATLAS FELIX production
 - FELIX boards test @LANL/BNL
 - Frontend RU services: daughter cards, transition boards, cables etc.
 - Ancillary systems - “adopt” ALICE ITS system
 - Power, slow control & monitoring etc.

A separate BNL R&D project, provides Staves & RUs


- no cost to MVTX project
- 84 ALICE/ITS-IB (modified) staves from CERN;
48+spares(2-inner layers+10%), in production
- 60 ALICE/ITS-RU from CERN
48+spares(12, 25%) , all produced

Project Status Update: 11/01/2019

- Confirmed long SamTec readout cables recently – last key electrical integration hardware R&D
 - 11.4m long cables, > 10m desired length
- MVTX mechanical design: excellent progress
 - Obtained quotes from outside companies based on preliminary designs for CYSS and End-Wheels
 - MVTX/sPHENIX integration/insertion workfest , 11/14 @BNL, MVTX/INTT/TPC...
- Early R&D fund released from BNL
 - MVTX mechanical engineering design, MIT/LANL
 - Preparation for Stave and RU acceptance test, LBNL, UT-Austin
- July 2019 MVTX Cost & Schedule Review Response submitted
 - WBS, PMP, Risk Registry, P6 updated
 - Updated PMP and review response submitted to DOE
 - We are ready for full production
- Plan to start the MVTX production activities as soon as funds available
 - Preparation for Stave and RU acceptance test & QA in US, LBNL and UT-A
 - Carbon structure prototype production, site selection etc
- Stave and RU production
 - Stave production in progress at CERN
 - 60 MVTX RUs delivered to CERN
 - Power mezzanine and transition boards produced at UT-A

Funding Profile (FY19+20, 21,22)

From July MVTX Review:



MVTX funding profile: FY20 -22

sPHENIX MVTX Budget Profile				
	FY20	FY21	FY22	Total
3.02.01 Management	\$233,668	\$209,596	\$101,338	\$544,602
3.02.02 Electronics	\$569,582			\$569,582
3.02.03 Mechanics and Assembly	\$1,370,727	\$307,183	\$113,468	\$1,791,378
3.02.04 Integration and Infrastructure	\$368,185	\$399,262	\$15,491	\$782,938
Performance Measure Baseline	\$2,542,162	\$916,041	\$230,297	\$3,688,500
Contingency	\$762,649	\$274,812	\$69,089	\$1,106,550
Total Project Cost	\$3,304,811	\$1,190,853	\$299,386	\$4,795,050

Can we move some FY20 (\$3.3M) activities to FY21 (\$1.2M), with minimal impact to the project?

Schedules – Smooth Funding Profile?

Possible Plan-B for FY20?


Candidates for possible delays, from FY20 to FY21:

- Carbon Structure production
- PU and CAEN PS
- Cooling system
- Delay stave test and detector assembly work at LBNL

Recent new quotes for carbon structures: CYSS & EndWheels


- Possible cost saving through commercial companies
- Carbon structure full production possible in FY20, w/ big saving

Fully aligned with sPHENIX via external milestones




MVTX Readout, Power and Controls Hardware Tested

Hardware status: Staves in production; RU produced, SamTec, PU & FELIX ready for production



one pixel



ALPIDE pixel:

- Shaping
- Digitization
- Zero-suppression
- 3x buffer

Interaction Region


9 Data (1.2Gbps)
1 Clock, 1 Control/Trigger

Samtec Twinax
"FireFly", ~10m

Regulated Power

Experimental Hall

Readout Unit
Front End



Power Board

CAN bus

GBT Optical Links

Control

Data (9.6 Gb/s max)

Trigger


CAEN Power supplies

Power

Counting House

DCS

Trigger & Clock



FELIX
Back End

ATLAS Front-End Link eXchange
(FELIX):

- sPHENIX Data Aggregation Module(DAM)

- Slow control
Mike's talk

MVTX Detector Electronics consists of three parts


Sensor-Stave (9 ALPIDE chips)

| **Front End**-Readout Unit

| **Back End**-FELIX/DAM

MVTX Global Mechanical System Integration

- MVTX mechanical system preliminary design:
 - Part-1: from MVTX staves to PP-1, all power PCB, 40cm
 - Part-2: length TBD later, from PP-1 to PP-3




Detector Supporting Structures: Part-1


- Near final design completed for CYSS, End-Wheels
- Obtained quotes from outside companies based on the latest designs for CYSS and End-Wheels
- LBNL cost estimate in progress

Next:


- Vendor selection
- Pre-production




MVTX Service Barrel – Part-2



ITS/IB Commissioning Setup @CERN, 9/2019



MVTX Global Mechanical System Integration




MVTX Installation & Insertion System

(WBS 2.x)


- Active discussions on mechanical design and fabrications
 - MIT, LANL, LBNL
 - CYSS, End-Wheels, Service Barrel

One-day MVTX/sPHENIX insertion system workshop
11/14/2019@BNL, Russ/OSI, Camelia et al

- MVTX, INTT, TPC ...




MVTX Installation Mockup




Beam Pipe Extension by CAD

(WBS 2.x)


- sPHENIX engineers meeting regularly with the CAD vacuum group;
- CAD will do some test welds to beam pipe material of the same OD to confirm;
- Beam pipe modification in the MoU with CAD.



2019 Fermilab Test Beam Highlights



11/01/19



MVTX Overview, Pre-QM sPHENIX Mtg. @Fudan Univ., China

15

Very Successful Test Beam @Fermilab

5/20-25, 6/17-22, 2019

- 4 staves
- 2 RUv1.1
- 1 PU
- 1 FELIX Server + RCDAQ
- sPHENIX GTM
- 11.4m Custom SamTec Cable
- Negative pressured cooling for staves

- 1 fully functioning 9-chip stave;
- 3 staves with a few broken sensors

120GeV p-beam
10kHz (30kHz)
Beam intensity:
30k ~ 120k ppp

4-stave telescope



SamTec: 11.4m
(2.6m+8.8m)

RU-2: 1 stave

RU-1: 3 staves

5m SamTec

Data & Control

Beam Trigger


Timing & Trigger

GTM

FELIX

Online Monitoring

RCDAQ




A full system with final sensor/readout* hardware:




- Multi-Stave + Multi-RU -> FELIX readout demonstrated
- sPHENIX GTM integrated
- Long readout SamTec cable certified
- Cooling system demonstrated

* RUv1.1 identical to the final RUv2 electrically

2019 MVTX Test Setup



Stave housing sits on a motion table which can be moved in (x, y) plane perpendicular to the nominal beam direction. It can also be rotated (+40, -40) degrees (see photo on right). Operation was done at counting house.






Online Analysis: Detector Misalignment & Hit Spatial Resolution

Typical stave offset,
Horizontally: $20 \times 30 \mu\text{m} = 600 \mu\text{m}$
Vertically: $5 \times 30 \mu\text{m} = 150 \mu\text{m}$


Hit spatial resolution:

$\text{peak_sigma_core} = 0.55 \text{ (pixel size)} = 15 \mu\text{m}$



Chip spatial resolution $= 15 / \sqrt{2} = 11 \mu\text{m}$



MVTX 4-Stave Telescope





Run 907, Number of Events: 37055



Beam angle: 40
(eta ~1)





Run 893, Number of Events: 228470



Offline Analysis: Cluster size vs Angle

To calibrate MC simulations and tracking

- Stave geometry, alignment
- Clustering



ALPIDE Sensor Operation Optimization


“ALICE Default Settings”

- “Pile up” integration time $\sim 5\mu\text{s}$


“Stretched Settings” for sPHENIX trigger study

- Pile up integration time $\sim 8\mu\text{s}$

64 cells \times 106nS = 6.8 μs





sPHENIX Trigger Latency $\sim 4.7\mu\text{s}$



sPHENIX Trigger Latency $\sim 6.8\mu\text{s}$



Preliminary Offline Analysis: A simple straight line fit

Track hit efficiency vs Trigger Delay



Offline Analysis: A simple straight line fit

Stave-3 Track hit resolution vs Trigger Delay




Confirmed New MVTX Long SamTec Readout Cables

8.8m + 2.6m = 11.4m (10m desired for sPHENIX; ALICE 8m cables)




11/01/19



MVTX Overview, Pre-QM sPHENIX Mtg. @Fudan Univ., China

11.4m SamTec Readout Cable Tested @CERN

- Double looped readout cables:
 - Effective length = 2 x 11.4 m = 22.8m
 - Data rate: 1.2Gbps
 - One overnight run, ~10hrs
 - Error rate < 1.4×10^{-14}
- **Production cable: 11m (>10m)**






Jo is testing the sPHENIX readout cables
Nice job!

11/01/19

MVTX Overview, Pre-QM sPHENIX Mtg. @Fudan Univ. China




sPHENIX Stave Production Started @CERN

- sPHENIX Production started in 9/2019
 - Bi-weekly meeting on Thursday 5PM/CERN (9AM/LANL)
- ~10 staves/month
 - Limited by Wire bonding , 2~3 staves/week
- Production period: ~10 months
 - Complete by the end of 2020
- Produce 12 HICs in 2019
- First ~21 staves available, 3/2020

First stave production kick-off meeting 10/24

- “The FPC production is well advanced, we have already the first batch of 24 pieces available.”
- ~100 golden chips available
- 1st sPHENIX HIC produced, “GOLD”, IBHIC-A201





The screenshot shows the agenda for the sPHENIX production videoconference. At the top, the ALICE logo is displayed next to the title "sPHENIX production". The meeting details are: Thursday 24 Oct 2019, 17:00 → 19:00, Europe/Zurich, at room 160/R-009 (CERN). The videoconference room is identified as "sPHENIX_production".

The agenda items are as follows:

- 17:00 → 17:20 HIC production status and plans**
 Speakers: Antonello Di Mauro (CERN), Dr Rajendra Nath Patra (CERN)
 Documents: Rajendra_sPHENIX-..., Rajendra_sPHENIX-..., sPHENIX HIC produ..., sPHENIX HIC produ...
- 17:20 → 17:40 Proposal for qualification test data exchange**
 Speaker: Markus Keil (CERN)
 Documents: 2019_10_24_sPheni..., 2019_10_24_sPheni...
- 17:40 → 17:50 AOB**

1st sPHENIX HIC Produced at CERN

- IBHIC-A201 & PWR extension clamp



IBHIC-A201

Accepted ALPIDE Chips from T847786 19T: A1*, A2, A4, A5, B1, B3, B7, C2, C3

*Dust removed from the back side.

Activities	Ins. after glue	Bonding	Ins. after bonding	Power test	Qualification test	HIC+SF+CP glue	= Stave Ready?
Done?	YES	YES	YES	YES [†]	YES [†]		

[†] With a new set up. PWR extension connection is made using a clamp. Pictures in the next slide.

IB HIC Qualification Test on 22.10.2019:

All gold.

Eyes are okay for all the drivers settings.


Qualification flag: **Gold** (Matrix: OK (**Gold**)/DTU: **OK**)

Final Production RU Boards Tested at UT-A

- 60 sPHENIX RUs produced at CERN
- 10 RUs produced for LANL R&D
- Tested 10 RU @UT-A, 10/14-18, 2019
 - All tested good, found one bad optical transceiver (1/30)
 - Jo, Yasser, Gerd
 - Alex T. joined for one day, readout firmware/software plan
- Plan to test the 60 sPHENIX RUs later

R&D at LANL

- Full ITS/IB QA testbench in operation
- Python GUI developed for telescope readout and control operation
- CAEN PS being tested



A Full Readout Chain System Test

- MVTX – readout in 6-subgroup
 - 48 staves + 48 RUs + 6 FELIXs

A complete readout chain:

8 staves + 8 RUs + 1 Felix + 1 RCDAQ Server

- Hardware in hand at LANL
 - 6 staves + 4 HICs(w/o carbon frame)
 - 10 RUv2.1
 - 2 FELIX v2.0
 - 2 PU
 - 1 sPHENIX GTM

Build a telescope of:

- 6 staves + 2 HICs
- 8 RUv2.1
- 1 FELIX
- 1 PU
- 1 GTM



A test beam later this year or 2020 (TBD)

- LBNL, 50MeV p-beam
- LANL, 800MeV p-beam
- Fermilab?

Summary

- Completed key R&D for readout integration
 - Full 9-chip stave readout per RU
 - Multi-RU readout per FELIX
 - Long readout cables
 - sPHENIX GTM
- Completed preliminary mechanical design
 - Vendor selection
 - Carbon structure (pre)production
 - Insertion mockup
- Improve MC detector response, clustering – in progress
 - Calibration data with incident angles, 0, 10, 20, 30, 40, 45
- Stave and RU production at CERN - in good progress
 - Acceptance test & QA in US
- July MVTX review response submitted to DOE
 - Expect project \$\$ distributed soon

We are ready for the full production and the physics!





backup

Near Term To-Do List

- Continue mechanical system design
 - CYSS, EW, SB
 - Global insertion system design and full mockup
- Carbon structure production
 - LBNL CF update
 - Follow up with US vendors for quotes
 - Select vendor(s) for pre-production
- RU acceptance QA at UTA
- Prepare for stave acceptance QA at LBNL
- FELIX production and test
 - Jointly with sPHENIX TPC, at BNL? Or LANL?
- 2019 test beam data analysis

sPHENIX Stave production at CERN

We will follow up the progress closely, production, Test & QA
- bi-weekly meetings with CERN

ITS system surface commissioning at CERN

Now --- May 2020

A good opportunity to learn about the system operation and controls;

Working on a coordinated effort within MVTX/sPHENIX,

Signup page,

<https://docs.google.com/spreadsheets/d/1YBAyouW8geJHUPpzRyLlZn4ePW4Yzl8glI5xI66N3ww/edit#gid=0>

A full “8-stave + 8-RU + 1-FELIX + 1-PU + 1 GTM” chain test

10 RU available

1 PU arrived at LANL from LBNL


8-stave/HICs telescope frame being designed

RU & FELIX Firmware update in progress


Slow control software & GUI

A possible test beam run later this year

sPHENIX Timeline




MVTX Readout and Power Cable Route



BNL has approved "non-halogen free" cables for sPHENIX

ALICE ITS/IB final readout cables: ~8m



sPHENIX MVTX: 7.9+m

Cable-A: 1.4 m

Cable-B: 6.5+ m


Power cable: 4.7+ m

Desired ~10m


SPHENIX Carbon Structure Production

- Visited WorkShape 9/19/2019
 - Walt and Ming, Simon
- WorkShape well prepared
 - Updated the design files
- MIT design work good progress, well ahead of time
 - Early Carbon structure review for pre-production, Nov/Dec 2019?
- Other companies, CA..
 - Received quotes for CYSS, End-Wheels
- LBNL in progress






ITS/IB RU and PU, w/ cables




PU & CAEN PS






MVTX Goals – the 2nd TB, 6/17-22, 2019

- Test and confirm optimal MVTX operation parameters for sPHENIX
 - Threshold scan, analogy shaping time etc.
 - Study chip hit efficiency vs trigger(strobe) latency
 - $dT = 1 \sim 10 \mu\text{S}$
 - Impact on occupancy & pileup
- Parameters predetermined from laser scan at LANL, in good progress
 - Single chip readout with MOSAIC with pulsed laser (\sim MIP)
 - Threshold and noise
 - Analogy shaping time
 - Strobe delay and length




Study MAPS Performance with Pulsed Laser @LANL

- Inject “MIP” signal, focused laser beam
 - 850 nm laser, 4ns wide pulse, ~1 MIP
 - 50kHz trigger
 - **Find optimal MAPS operating parameters**



Laser Scan Data – Pixel Hit Efficiency vs Trigger Delay

One of “Stretched Settings” for sPHENIX trigger
MAX: 64 cells x 106nS = 6.8uS




09:04:12

MVTX Test Beam, May 2019

FTBF Status

Mtest Energy: 120 GeV

MTest Mode: Proton



- Other Parameters
- Scintillator Counters
 - Cherenkov Parameters
 - Pinhole Collimators
 - Mtest - 17
 - TTL Timing
 - NIM Timing Marks
 - MT6 Environment
 - MCenter Environment

MT6SC1	MT6SC2	MT6SC3	MT6SC4
14926 Cnts	14230 Cnts	12985 Cnts	13786 Cnts

Please request intensity from the MCR using F:MTSCL5

SC1+SC2+SC3+Spill (F:MTSCL5)	12388 Cnts
MWPC Triggers	4577 Cnts
Experiment Triggers	13786 Cnts
Next Spill	52 Sec



2 RUs,
PU,
PS

Motion Table
(X,Y,Phi)



4-stave
Telescope

120GeV p-beam



Negative
Pressure Cooling
System


First Collision Signals

sPHENIX GTM



Staves, RUs, PU etc.





120GeV p-beam


Telescope

RUs & PU

Cooling System;
negative pressure
@ -30%ATMP (-5PSI)

11/01/19

MVTX Overview, Pre-QM sPHENIX Mtg. @Fudan Univ., China




120GeV p-beam


Telescope

48

When MAPS
parameters off the
optimal point, less hits
collected




No hits seen when
MAPS parameters far-
off the optimal point



Installation




3-D event Display: p+Pb collision




Offline Analysis: Cluster size vs Angle

Run 877, angle – 30 dgr




Cluster Size = 2.7



Offline Analysis: Cluster size vs Angle


Run , angle = 40



Cluster Size ~ 3.0

More work follows by Yasser, Sanghoon et al
Everyone is welcome to join the effort!


- Stave geometry
- Stave alignment
- Clustering
- Tracking
- Update MVTX MC response in GEANT




Run Types – Details being documented in MVTX wiki

From Xiaochun

Run0978




Horizontal stave scans (many good runs)




Vertical stave scans

Run0877




Angular stave scans and tilted runs



Extruded aluminum & Lead-block runs

Run1040



Electron beam at 5 GeV (one long run)

Most VisitedGetting StartedMAPS-based Vertex...MVTX Technical De...sphenix-mvtx · GitLabIntro | sPHENIX Coll...

Sphenix talk preferences wat

page

discussion

edit

history

move

watch

PHENIX

navigation

- Main page
- Community portal
- Current events
- Recent changes
- Random page
- Help

sphenix detector

- Magnet
- EMCAL
- HCAL
- Tracking
- TPC
- MVTX
- INTT
- Electronics
- Beam tests
- Software

collaboration

- Meetings
- Listservers
- Document database

Search

Go










Search

tools

- What links here
- Related changes
- Upload file
- Special pages
- Printable version
- Permanent link
- Page information

LongRunList

[edit]

pKey	run	time	Beam Angle	tableX (mm)	tableY (mm)	beamEnergy (GeV)	beamParticle	comment	eventDisplay
1	0831								
2	0847								
3	0848	5-20-2019 19:34:37		1095.5	270.1	120	Proton		
4	0849	5-20-2019 19:34:37		1095.5	270.1	120	Proton		
5	0850	5-20-2019 19:34:37		1095.5	270.1	120	Proton		
6	0851	5-20-2019 19:34:37		1095.5	270.1	120	Proton		
7	0852	5-20-2019 19:34:37		1095.5	270.1	120	Proton		
8	0853	5-20-2019 19:34:37		1095.5	270.1	120	Proton		
9	0854	5-20-2019 19:34:37		1095.5	270.1	120	Proton		

- Data run-log in sPHENIX Wiki, Nice work by Xiaochun et al. @GSU
- Jin's test beam analysis framework Offline analysis in progress