

# MVTX Overview (WBS 3.2)

Ming Liu, LANL


April 9-11, 2019

BNL Director's Review


# Outline

- MVTX science & technology
- MVTX scope
- Cost & schedule
- Status & highlights
- Issues and concerns

**MVTX:**  
**Monolithic-active-pixel-sensor based VerTeX detector**



# The sPHENIX Detectors






## Tracking system upgrade:

- INTT (WBS 3.1)
- MVTX (WBS 3.2)

# MVTX Enables the 3<sup>rd</sup> Science Pillar

1. Jets
2. Upsilon
3. Open Heavy Flavor

- Bottom quarks are heavy (4.2 GeV)
- Produced in initial collision, probe QGP evolution
- Well controlled in pQCD
- Access fundamental transport properties of QGP



- Precision tracker + High rate capability  
→ Precision bottom observables over wide scales in p+p, p+A and A+A
- Initial observables:
  - **B-meson @  $p_T < 10$  GeV/c**
  - **b-jet @  $15 < p_T < 50$  GeV/c**

# MVTX Technical Overview



Ross & Yuan's talks

Service cone: signal, power, cooling  
and mechanical support

CYSS: Cylindrical Shell Structure

Extended power FPC

End-Wheel



MVTX  
parameters

	Layer 0	Layer 1	Layer 2
Radial position (min.) (mm)	23.7	31.4	39.1
Radial position (max.) (mm)	28.0	35.9	43.4
Length (sensitive area) (mm)	271	271	271
Active area (cm <sup>2</sup> )	421	562	702
Number of pixel chips	108	144	180
Number of staves	12	16	20


# Monolithic Active Pixel Sensors (MAPS)

## The Next-Generation, State-of-the-Art Pixel Tracker

### Advantages of ALICE Pixel DEtector (ALPIDE) sensor:

- Very fine pitch ( $27\mu\text{m} \times 29\mu\text{m}$ ), for superb spatial resolution
- High efficiency ( $>99\%$ ) and low noise ( $<10^{-6}$ ), for excellent tracking
- Time resolution, as low as  $\sim 5 \mu\text{s}$ , for less pileup
- Ultra-thin/low mass,  $50\mu\text{m}$  ( $\sim 0.3\% X_0$ ), for less multiple scatterings
- 0.5M channels with on-pixel digitization, for zero-suppression and fast readout
- Low power dissipation,  $40\text{mW}/\text{cm}^2$ , for minimal service materials


Flexible Printed Circuit(FPC)



An ideal detector for QGP physics!

A 9-chip MAPS stave, 1.5cm x 27cm

### ALPIDE design




### Tower Jazz 0.18 $\mu\text{m}$ CMOS

- feature size 180 nm
- metal layers 6
- gate oxide 3nm

substrate:  $N_A \sim 10^{18}$   
epitaxial layer:  $N_A \sim 10^{13}$   
deep p-well:  $N_A \sim 10^{16}$


ALPIDE sensor:

1.5cm x 3.0cm, 0.5M pixels




# MVTX Readout, Power and Controls

Jo's talk





one pixel




ALPIDE pixel:

- Shaping
- Digitization
- Zero-suppression
- 3x buffer

Interaction Region



Experimental Hall



FELIX Back End

ATLAS Front-End Link eXchange (FELIX):


sPHENIX Data Aggregation Module (DAM)

Counting House

MVTX Detector Electronics consists of three parts

**Sensor-Stave** (9 ALPIDE chips) | **Front End-Readout Unit** | **Back End-FELIX/DAM**


# MVTX Detector in sPHENIX



- Mechanical structure design
  - Design & FEA, LANL/MIT
  - End Wheels
  - Cylindrical structure shells
  - Detector service half barrels
  - Service patch panels
  - Global interface
- Mechanical structure fabrication
  - Composite structures, LBNL
  - Non-composite structures, MIT
  - Installation tooling etc., MIT/LANL/LBNL/BNL
- Ancillary systems – “adopt” ALICE/ITS
  - Cooling plant, MIT/BNL
  - Slow control & monitoring etc., MIT/GSU
- MVTX electronics
  - Backend FELIX and cables
  - Integration into sPHENIX DAQ
  - Power system
- Detector assembly & test
  - Stave QA & half detector assembly @LBNL
  - System test & integration @LBNL/BNL
- Installation & commissioning, by all
  - Pre-installation commissioning @BNL
  - Installation @IR

Early generic R&D accomplished through LANL LDRD  
- Readout integration  
- Detector conceptual design


# MVTX Collaborators & Institution Roles



- Los Alamos National Laboratory (LANL)** : Overall readout electronics and mechanical system integration, project management.
- Brookhaven National Laboratory (BNL)** : Global system integration and services, safety and monitoring, project management.
- Lawrence Berkley National Laboratory (LBNL)** : Carbon structure production, LV and HV power system, full detector assembly and test, project management.
- Massachusetts Institute of Technology (MIT/Bates)** : Global mechanical system integration and cooling.
- Massachusetts Institute of Technology (MIT)** : Stave assembly and test at CERN.
- University of California at Los Angeles (UCLA)** : Simulation and readout testing.
- University of California at Riverside (UCR)** : Detector assembly and test, simulations.
- Central China Normal University (CCNU/China)**: MAPS chip and stave test at CERN and/or CCNU.
- Charles University (CU/Czech)** : MAPS stave production and QA.
- University of Colorado (UCol)** : *b*-jet simulations and future hardware.
- Czech Technical University (CTU/Czech)** : MAPS stave production and QA at CERN.
- Florida State University (FSU)** : Offline software and simulations.
- Georgia State University (GSU)** : Online software and trigger development.
- Iowa State University (ISU)** : Detector assembly and test, simulations.
- National Central University (NCU/Taiwan)\*** : Stave assembly and test, simulations.
- University of New Mexico (UNM)** : Cabling & connectors.
- New Mexico State University (NMSU)** : Tracking algorithm and physics simulations.
- Purdue University (PU)**: Detector assembly and test, simulations.
- Univ. of Science and Technology of China (USTC/China)** : MAPS chip and stave test, simulations.
- Sun Yat-Sen University (SYSU/China)** : MVTX detector and physics simulations.
- University of Texas at Austin (UTA)** : MVTX readout electronics integration, Readout Units production and test.
- Yonsei University (YSU/Korea)** : MAPS chip production QA, readout electronics test and simulations

# Schedule Drivers

- Budget availability
  - Final engineering design of the mechanical system
  - Production of support structures
- Mechanical structures
  - Detector and interface system design
  - Carbon structure fabrication
- Detector assembly and test
  - Assembly jigs design and fabrication
  - Detector assembly & QA
  - Metrology
- Final installation in IR
  - Last detector to be installed



# Cost Drivers

MVTX Budget by L3 in AYk\$		Burdened /Esc.		
WBS	Level 2 WBS Description	OPC	TEC	Total
3.2.01	Project Management	\$0	\$642	<b>\$642</b>
3.2.02	Electronics	\$0	\$665	<b>\$665</b>
3.2.03	Mechanics and Assembly	\$0	\$2,001	<b>\$2,001</b>
3.2.04	Integration and Installation	\$0	\$1,023	<b>\$1,023</b>
	<b>Sub-total</b>	<b>\$0</b>	<b>\$4,331</b>	<b>\$4,331</b>
	<b>Contingency</b>	<b>\$0</b>		<b>\$0</b>
	<b>Total Project Cost</b>	<b>\$0</b>	<b>\$4,331</b>	<b>\$4,331</b>

Mechanical design and fabrication

- CYSS
- End wheels
- Service barrel
- Global interface

# Basis of Estimate & Resource-Loaded Schedules SPHENIX

- Electronics: production
  - FELIX: ATLAS/sPHENIX production, LANL/LDRD
  - RU services, cables: ALICE/ITS production, LANL/LDRD
  - Power boards: ALICE/ITS production, LANL/LDRD
  - CAEN bulk PS: Quotes from CAEN, ALICE/ITS production, LANL/LDRD
- Mechanics & Integration: design and production
  - CYSS, End wheels, Service barrel: ALICE/ITS
  - Integrations: Recent experience at RHIC, HFT/STAR, FVTX/PHENIX

**WBS Number: 3.2.2.3 Backend Electronics - FELIX**

## MVTX BoE Doc

**Technical scope:**  
This item contains all the backend readout electronics FELIX boards required for MVTX readout.

**Work statement:**  
Produce 8 FELIX boards to integrate MVTX readout electronics into the sPHENIX DAQ system.

**Assumptions used in developing estimate:**  
We will use the ATLAS FELIX v2.0 PCIe board developed by the BNL group for the ATLAS upgrade. The FELIX board production quote for sPHENIX was obtained in 2018, about \$8K per board. A total of 8 FELIX boards ( 6 + 2 spares) are required for MVTX.

**Cost Summary:**

Total (K)	M&S	Labor	Contingency (average)
122	103	19	25%

**BROOKHAVEN NATIONAL LABORATORY**

**sPHENIX MVTX Project Detailed Schedule**  
Budgeted Cost Included  
Data Date: 01-Oct-18 Published: 02-Apr-19 14:38

Activity ID	Activity Name	CAM	At Compl. Duration	Start	Finish	Total Float	Hours	Direct FY19\$	Burd AFS - M&S	Burd AFS - Labor	Burd AFS - M&S	Burd AFS - Labor	Total
S110400	ship from CERN to LBNL - Batch 1	Liu, Ming	7	27-Jun-19	08-Jul-19	0	600	0	600	\$0	\$7,500	\$0	\$7,500
S110500	ship from CERN to LBNL - Batch 2	Liu, Ming	7	25-Sep-19	03-Oct-19	268	0	600	\$0	\$7,564	\$0	\$7,564	
S110600	ship from CERN to LBNL - Batch 3	Liu, Ming	7	27-Dec-19	07-Jan-20	219	0	600	\$0	\$7,650	\$0	\$7,650	
S110700	ship from CERN to LBNL - Batch 4	Liu, Ming	7	27-Mar-20	06-Apr-20	169	0	600	\$0	\$7,650	\$0	\$7,650	
POM028_3.02.3.02.03.02	Carbon Structures		741	01-Apr-19	17-Mar-22	0	5774	368511	\$910,025	\$472,154	\$1,382,179		
POM028_3.02.3.02.03.02.01	Mechanics Detector Design		80	01-Apr-19	23-Jul-19	0	640	0	\$167,952	\$0	\$167,952		
S110800	Develop MAPS inner tracker mechanical model	Liu, Ming	80	01-Apr-19	23-Jul-19	0	640	0	\$167,952	\$0	\$167,952		
POM028_3.02.3.02.03.02.02	End Wheels		277	24-Jul-19	28-Aug-20	54	502	72000	\$73,964	\$90,875	\$164,839		
S110900	Design End-wheels	Liu, Ming	15	24-Jul-19	13-Aug-19	54	120	0	\$36,658	\$0	\$36,658		
S111000	Prototype End-wheels - M&S	Liu, Ming	30	14-Aug-19	25-Sep-19	54	0	10000	\$0	\$12,500	\$12,500		
S111100	Prototype End-wheels - Labor	Liu, Ming	30	14-Aug-19	25-Sep-19	54	12	0	\$2,305	\$0	\$2,305		

**FELIX**

Activity ID	Activity Name	Resource	Start	Finish	Hours	M&S	Labor	Contingency	Total
POM028_3.02.3.02.03.02.02	FELIX 2.0		01-Apr-19	03-Apr-20	392	186	88400	\$18,588	\$103,640
S103000	Produce Felix 2.0 first production unit - Labor	Liu, Ming	01-Apr-19	19-Jun-19	218	16	0	\$307	\$3,073
S103100	Procure Optical Fiber - Labor	Liu, Ming	01-Apr-19	19-Sep-19	414	2	0	\$307	\$307
S103200	Produce Felix 2.0 first production unit - M&S	Liu, Ming	01-Apr-19	19-Jun-19	218	0	20000	\$0	\$22,778
S103300	Procure Optical Fiber - M&S	Liu, Ming	01-Apr-19	19-Sep-19	414	0	50	\$0	\$63
S103400	Test/OA 1st Felix Unit and Fibers	Liu, Ming	20-Sep-19	03-Oct-19	414	40	0	\$0	\$0
S103500	Procure 7 Felix 2.0 Remaining Units - Provide Requirements to Procurement	Liu, Ming	06-Nov-19	13-Nov-19	392	6	0	\$1,187	\$1,187
S103600	Procure 57 Optical Fiber Sets - Labor	Liu, Ming	06-Nov-19	06-Dec-19	462	2	0	\$396	\$396
S103700	Procure 57 Optical Fiber Sets M&S	Liu, Ming	06-Nov-19	06-Dec-19	462	0	2850	\$0	\$3,634


Carbon Structures

Labor, M&S

# Resource Distribution

MVTX in P6

Summary MVTX Labor + M&S Cost Profile in Burdened At-Year \$  
by Level 3 WBS



WBS Code and Name	FY17	FY18	FY19	FY20	FY21	FY22	FY23	Burdened AY\$	Direct FY19\$
3.02.01 MVTX Project Management			\$ 110,219	\$ 216,751	\$ 216,269	\$ 98,244		\$ 641,483	\$ 373,537
3.02.02 MVTX Electronics			\$ 171,762	\$ 493,205				\$ 664,967	\$ 506,824
3.02.03 MVTX Mechanics and Detector Assembly			\$ 409,513	\$ 997,208	\$ 529,814	\$ 64,163		\$ 2,000,698	\$ 1,289,696
3.02.04 MVTX Integration and Infrastructure			\$ 150,963	\$ 538,325	\$ 317,878	\$ 15,892		\$ 1,023,058	\$ 651,708
<b>Grand Total</b>			<b>\$ 842,457</b>	<b>\$ 2,245,489</b>	<b>\$ 1,063,961</b>	<b>\$ 178,298</b>		<b>\$ 4,330,205</b>	<b>\$ 2,821,765</b>

# MVTX Schedules and Milestones SPHENIX



SPHENIX:

★ CD1/3a

★ PD2/3


★ Installation

★ 1<sup>st</sup> collisions

Generic R&D  
Sensors for RHIC

MVTX

Feb. 2019, in P6




Today

# Status and Highlights



- Full readout chain demonstrated through LANL LDRD
  - Successful Fermilab Test Beam run in 2018
- Modified stave certified through LANL LDRD
  - Successfully tested at CERN
  - Radiation hardness verified at CERN
- Mechanical system integration MVTX+INTT
  - sPHENIX tracking optimized with 2-layer INTT configuration
  - Mechanical design being updated and 3-D mockup demonstrated
- Readout cables
  - BNL approved the use of SamTec non-Halogen-free cables
    - Electrically better & mechanically compact
    - ALICE confirmed performance with 8m long Halogen-free cables
    - For MVTX, ~10m very likely work (30AWG/sPHENIX vs 32AWG/ALICE)
  - Samples (6.5 ~ 11.5m long) ordered for R&D test at LANL
    - To be tested in coming months




# MVTX Full Readout Chain Demonstrated (3/2018) SPHENIX



**Fermilab Test Beam: Feb-Mar, 2018**





- Tracking spatial resolution:  $< 5 \mu\text{m}$
- Hit efficiency:  $> 99.5\%$



# Confirmed HIC with Extended 40(60)cm Power FPC SPHENIX

- Built and tested two HICs at CERN in 9/2018
  - **No change in sensor performance (noise, threshold) observed, as expected;**



Followed identical ALICE IB QA test procedure, with a 8m SamTec cable!

# Sensor Irradiation Test – OK at 2.7Mrad

- Continuous effort by ALICE (@NPI, Czech)
- BNL Director's review recommendation:  
- **Test sensors up to 1Mrad**

ALICE/ITS report: 2.7 Mrad

<https://indico.cern.ch/event/758048/>


## Conclusion

Irradiated ALPIDE sensor (2700 krad) over a large range of threshold settings

has :

- 1) good efficiency up to threshold  $\sim 190 e^-$  ( $I_{thr} = 100$  DAC units) at  $V_{bb} = -3$  V,  $V_{casn} = 90$ ,  $V_{casn2} = 102$
- 2) fake hit rate remains orders of magnitude smaller than the requirement ( $\ll 10^{-6}$ )


## Irradiated chip#41 (2.7Mrad) : efficiency & fake hit rate



red line - fake hit rate- sensitivity limit of ALPIDE  
black line - efficiency - the project goal ( 99% )

For non irradiated 2 noisy pixels were masked out.  
No pixel was masked out for the 2.7Mrad chip.

# MVTX + INTT 3-D Mockup (11/2018)



A



B

**Office of System Integration**

– led by Mickey & Bob,  
a team of engineers and physicists

MVTX and INTT


Space conflict resolved!



D



C



# Latest Project Update: MVTX Workshop

Feb. 28 – Mar. 2, 2019, MVTX/HF Workshop @LBNL




**Updated Cost & Schedule  
under review;  
Significant cost saving possible**



**Discussed major carbon structures'  
design & production cost, line by line;  
Also LBNL production schedule**

# Carbon Structures – Work in Progress

- Conical sectors are expensive!
- A new design under development to avoid the conical structures, MIT/LANL



- Budget availability
  - Funding for final mechanical system design work
    - Early R&D to reduce high production contingency
  - Preparation for Stave acceptance test/QA/storage at LBNL (3 months lead time)
  - Schedule is closely tied to the funding level
- Carbon structures
  - Cost and schedule, high contingency in cost
  - Window of opportunity at LBNL before ATLAS production
  - Other possible production sites (Italy, France, Korea ...)
- Mechanical system integration
  - sPHENIX beam pipe modification, under discussion with CAD
  - Readout cables, cooling etc.
  - MVTX+INTT+TPC... global support structure design

# Summary

- MVTX enables the 3<sup>rd</sup> science pillar
- MVTX detector design & construction
  - As a separate upgrade project from the baseline sPHENIX MIE
  - Engineering design work in progress, MIT/LANL/LBNL et al
    - **Need budget now for the final engineering design work**
  - Construction and assembly work planned for late 2019
- Project integrated into the sPHENIX P6
  - Latest Cost & Schedule under review, significant cost saving possible
  - To be implemented in P6 after this review
- Successful generic R&D through LANL LDRD support
  - Readout integration
  - Stave modification
  - Mechanical system conceptual design
- MVTX is ready to receive project funding

# backup

---



## Stave and RU procurement readiness

- Completed sensor/HIC/stave evaluations at CERN
  - Built, tested and confirmed two HICs with 40cm and 60cm long power FPC
  - Sensors irradiated up to 2.7MRad, no issues (updated 9/18/2018).
- **Addressed all recommendations on stave/sensor R&D**

[https://docs.google.com/document/d/1vsm\\_G7ZLgqv-kBZqK0jF69T\\_Nx2Uwk0Zxv86jRVxybw/edit?usp=sharing](https://docs.google.com/document/d/1vsm_G7ZLgqv-kBZqK0jF69T_Nx2Uwk0Zxv86jRVxybw/edit?usp=sharing)

## **Cost are set for staves & RUs, procurement through US-ALICE/UTK**

- Technical specs document completed for production, BNL/DOE agreed
- sPHENIX RU and stave production starts ~May 2019
- MVTX/INTT mechanical integration
  - Mechanical design being updated and 3-D mockup demonstrated
  - Inner tracking task force completed evaluation, preferred INTT-layers =2
- Readout cables
  - BNL approved the use of SamTec blue cables
    - Electrically better & mechanically compact
    - ALICE confirmed signal performance with 8m long readout cables. For MVTX, 10m very likely works (30AWG/sPHENIX vs 32AWG/ALICE), to be confirmed by on-going R&D at LANL
  - Samples ordered for system integration mockup and test

# Stave and RU Production QA Plan Documents Available



<https://indico.bnl.gov/event/4729/>

## Staves

- Purchase 84 staves from ALICE/CERN
  - **48 + 28(spares for 2 inner layers) + 8 spares**
  - **Production following the completion of ALICE ITS/IB**
  - **Starting ~Oct. 2018, will last 6-12 months**
  - **Fully tested at CERN before shipping to US**
    - All Gold/Silver staves (same as ALICE IB)
    - A LANL postdoc (Dr. Yasser Morales) oversees production QA at CERN
- Acceptance QA at LBNL
  - **Full test and QA**
    - Electrical
    - Mechanical
  - **Detector assembly at LBNL**




## Readout Units

- Purchase 60 RUs from ALICE/CERN
  - **48 + 12 spares(20%)**
  - **To be part of ALICE production**
    - Cost saving
    - Minimize technical risks
  - **Initial test at CERN**
- Acceptance QA at UT-Austin
  - **Full test**
  - **LANL as the 2<sup>nd</sup> test site**

# 2019 Test Beam: 4-stave Telescope

Jo's talk


- Scheduled for May 22-29, at Fermilab
- Additions compared to the 2018 test beam:
  - Staves (from single chips)
  - Full-length MVTX signal cables (from 5 m off-the-shelf cables)
  - FELIX v2.0 (from v1.5)
  - Cooling system
  - Power board
  - sPHENIX GTM



Full test of all components of the MVTX detector - LDRD “stretch goal”


# MVTX Readout and Power Cable Rout

Jo's talk



BNL has approved "non-halogen free" cables for sPHENIX

ALICE ITS/IB final readout cables: ~8m



sPHENIX MVTX: 7.9+m

Cable-A: 1.4 m

Cable-B: 6.5+ m

Power cable: 4.7+ m

On-going R&D for ~10m

# MVTX in P6 (fully Burd. & Esca.)




BROOKHAVEN NATIONAL LABORATORY		sPHENIX MVTX Project Detailed Schedule											Budgeted Cost Included						
											Data Date: 01-Oct-18 Published: 02-Apr-19 12:38								
Activity ID	Activity Name	CAM	At Compl. Duration	Start	Finish	Total Float	Hours	Direct FY15-M&S	Burd AYS-Labor	Burd AYS-M&S	Burd AYS-Total	2015	2016	2017	2018	2019	2020	2021	2022
												FY15	FY16	FY17	FY18	FY19	FY20	FY21	FY22
POM02B_3.02	POM02 sPHENIX WBS 3.02 Preliminary Baseline [MVTX]		1281	01-Feb-17 A	17-Mar-22	0	26695	1266751	\$2,760,452	\$1,569,754	\$4,330,205								
POM02B_3.02.3	Silicon Detectors		1281	01-Feb-17 A	17-Mar-22	0	26695	1266751	\$2,760,452	\$1,569,754	\$4,330,205								
POM02B_3.02.3.00	(Temporary) External Placeholder Milestones in WBS 3x		1169	01-Feb-17 A	01-Oct-21	112	0	0	\$0	\$0	\$0								
EXT100090	[External Activity] Initial Project Funding Release	Sourikova, Irina	0	01-Feb-17 A			0	0	\$0	\$0	\$0					01-Feb-17 A			
EXT317000	[External Activity] Design/Safety Reviews Complete, Internal Detector Structural Support Released for Production	Ponteri, Chris	0		19-Jul-19*		319	0	0	\$0	\$0								19-Jul-19*
EXT101010	[External Activity] FY20 Funding Available	Sourikova, Irina	0	01-Oct-19*			417	0	0	\$0	\$0								01-Oct-19*
EXT147100	[External Activity] Procure TPC DAM Felix 2.0 Boards - Contract Award(s)	Hemmick, Tom	0	06-Nov-19*			392	0	0	\$0	\$0								06-Nov-19*
EXT101015	[External Activity] FY21 Funding Available	Sourikova, Irina	0	01-Oct-20*			362	0	0	\$0	\$0								01-Oct-20*
EXT101016	[External Activity] FY22 Funding Available	Sourikova, Irina	0	01-Oct-21*			112	0	0	\$0	\$0								01-Oct-21*
POM02B_3.02.3.02	MVTX		741	01-Apr-19	17-Mar-22	0	26695	1266751	\$2,760,452	\$1,569,754	\$4,330,205								
POM02B_3.02.3.02.00	Temporary		248	01-Apr-19	26-Mar-20	169	0	0	\$0	\$0	\$0								
POM02B_3.02.3.02.00.01	ALICE ITS Key Tasks		0	01-Apr-19	01-Apr-19	255	0	0	\$0	\$0	\$0								
S100000	ALICE ITS RU Production Start	Liu, Ming	0	01-Apr-19*			255	0	0	\$0	\$0					01-Apr-19*			
POM02B_3.02.3.02.00.02	MVTX Stave Production at CERN		248	01-Apr-19	26-Mar-20	169	0	0	\$0	\$0	\$0								
S100100	Stave Production - Batch 1	Liu, Ming	62	01-Apr-19	26-Jun-19	169	0	0	\$0	\$0	\$0								
S100200	Stave Production - Batch 2	Liu, Ming	62	27-Jun-19	24-Sep-19	169	0	0	\$0	\$0	\$0								
S100300	Stave Production - Batch 3	Liu, Ming	62	25-Sep-19	26-Dec-19	169	0	0	\$0	\$0	\$0								
S100400	Stave Production - Batch 4	Liu, Ming	62	27-Dec-19	26-Mar-20	169	0	0	\$0	\$0	\$0								
POM02B_3.02.3.02.00.03	sPHENIX Milestones		0			0	0	0	\$0	\$0	\$0								
POM02B_3.02.3.02.01	MVTX Project Management		741	01-Apr-19	17-Mar-22	0	1858	37762	\$592,839	\$48,644	\$641,483								
S100500	Milestone Start MVTX	Liu, Ming	0	01-Apr-19			0	0	\$0	\$0	\$0								01-Apr-19
S100600	Project Manager	Liu, Ming	741	01-Apr-19	17-Mar-22	0	1238	0	\$395,226	\$0	\$395,226								
S100700	Mechanical Integration Engineer	Liu, Ming	741	01-Apr-19	17-Mar-22	0	310	0	\$98,806	\$0	\$98,806								
S100800	Electronics Integration Engineer	Liu, Ming	741	01-Apr-19	17-Mar-22	0	310	0	\$98,806	\$0	\$98,806								
S100900	Travel FY19	Liu, Ming	128	01-Apr-19	30-Sep-19	112	0	6250	\$0	\$7,813	\$7,813								
S101000	MVTX Construction Start Approval	Liu, Ming	0	01-Apr-19*			0	0	\$0	\$0	\$0					01-Apr-19*			
S101100	Travel FY20	Liu, Ming	251	01-Oct-19	30-Sep-20	112	0	12500	\$0	\$15,938	\$15,938								
S101200	Travel FY21	Liu, Ming	250	01-Oct-20	30-Sep-21	112	0	12500	\$0	\$16,256	\$16,256								
S101300	Travel FY22	Liu, Ming	112	01-Oct-21	17-Mar-22	0	0	6512	\$0	\$8,638	\$8,638								
S101400	MVTX Assembly Complete and Ready for Installation	Liu, Ming	0		17-Mar-22		0	0	\$0	\$0	\$0								17-Mar-22
POM02B_3.02.3.02.02	MVTX Electronics		286	01-Apr-19	19-May-20	363	3863	395448	\$195,007	\$469,960	\$664,967								
POM02B_3.02.3.02.02.01	Readout Unit (RU)		193	01-Apr-19	07-Jan-20	453	1137	82428	\$85,282	\$100,435	\$185,717								

# MVTX MS Project 1/4(for estimation) SPHENIX

Thu 4/18/19

MVTX-Barrel-120718-04042019




# MVTX MS Project 2/4



Thu 4/4/19

MVTX-Barrel-120718-0402419




# MVTX MS Project 3/4



Thu 4/4/19

MVTX-Barrel-1207.18-04042019



# MVTX MS Project 4/4



Thu 4/4/19

MVTX-Barrel-120718-04042019

ID	Task Mode	WBS	Task Name	Resource	Duration	Start	Finish	Fixed Cost	Calculated Fixed Cost	Resource Names	Resource Costs	Cost
189		3.2.4.5.3	Assemble & Test Cooling System		20 days	Fri 2/25/22	Thu 3/24/22	\$0	\$0	TECH4_Ins	\$16,640	\$16,640
190		3.2.4.5.8	Complete System Test at BNL		3 mons	Fri 3/25/22	Thu 6/16/22	\$0	\$0	SCI3_Ins	\$0	\$0
191		3.2.4.5.4	test RU at BNL		0.8 wks	Wed 11/13/19	Tue 11/19/19	\$0	\$0	SCI3_Ins	\$12,608	\$12,608
192		3.2.4.5.5	test FELIX at BNL		0.8 wks	Wed 7/8/20	Tue 7/14/20	\$0	\$0	SCI3_Ins	\$12,608	\$12,608
193		3.2.4.5.6	PS tests at BNL		0.5 wks	Tue 2/2/21	Thu 2/4/21	\$0	\$3,920	POSTD_Engineer	\$3,920	\$3,920
194		3.2.4.6	Installation and Commissioning		387 days	Wed 7/7/21	Thu 12/29/22	\$0	\$326,944	Mech Tech,Physicist,Elec tech,STAFFPHY	\$326,944	\$326,944
195		3.2.4.6.1	Installation Prep		10 days	Wed 7/7/21	Tue 7/20/21	\$0	\$15,520	Mech Tech,Physicist	\$15,520	\$15,520
196		3.2.4.6.2	Installation Review		1 day	Wed 7/21/21	Wed 7/21/21	\$0	\$2,320	Physicist,Engineer	\$2,320	\$2,320
197		3.2.4.6.3	Install FELIX		2 days	Thu 7/22/21	Fri 7/23/21	\$0	\$5,168	SCI3_Ins	\$5,168	\$5,168
198		3.2.4.6.4	Install Optical fibers		1 wk	Mon 7/26/21	Fri 7/30/21	\$0	\$8,120	TECH4_Ins	\$8,120	\$8,120
199		3.2.4.6.5	Install RU		1 wk	Mon 8/2/21	Fri 8/6/21	\$0	\$19,320	SCI3_Ins	\$19,320	\$19,320
200		3.2.4.6.6	Install Samtec Cables		1 wk	Mon 8/9/21	Fri 8/13/21	\$0	\$8,120	TECH4_Ins	\$8,120	\$8,120
201		3.2.4.6.10	Electronics Integration		6 mons	Mon 8/16/21	Fri 1/28/22	\$0	\$158,136	PROF4_Ins	\$158,136	\$158,136
202		3.2.4.6.7	Install Half-Barrel 1		1 mon	Fri 7/1/22	Thu 7/28/22	\$0	\$26,320	MECHTE	\$26,320	\$26,320
203		3.2.4.6.8	Install Half-Barrel 2		1 mon	Fri 7/29/22	Thu 8/25/22	\$0	\$26,320	MECHTE	\$26,320	\$26,320
204		3.2.4.6.9	Commissioning		90 days	Fri 8/26/22	Thu 12/29/22	\$0	\$57,600	Physicist,Engineer	\$57,600	\$57,600
205		3.2.5	Ready for beam		0 days	Thu 12/29/22	Thu 12/29/22	\$0	\$0		\$0	\$0

