

MVTX Summary

Ming Liu Los Alamos National Laboratory MVTX BNL Director's Review July 19-20, 2018

Summary



- sPHENIX overview Dave/Gunther
 - Compelling science
- MVTX overview Ming
 - Status and highlights
- Readout integration Alex/Sho
 - #1, 2, 3
- Staves Leo/Grazyna
 - #1, 3, 4, 5, 6, 7, 8
- Readout Units Jo
 - #1, 3, 4, 5, 6, 7, 8
- INTT overview Rachid
 - Important for tracking
- Mechanical integration Walt/Dan
 - #10
- Tracking simulation Tony
 - #9
- Summary Ming
 - YES, we are ready, #1, 8

Associate Laboratory Director for Nuclear and Particle Physics



Berndt Mueller Building 510F P.O. Box 5000 Upton, NY 11973-5000 Phone 631 344-5820 Frax 631 344-5820 bmueller@bnl.gov

managed by Brookhaven Science Associates for the U.S. Department of Energy

www.bnl.gov

Review of the sPHENIX pixel vertex detector, MVTX

July 19-20, 2018 Charge to the review committee

The purpose of the review is to evaluate the maturity of the design of the sPHENIX pixel detector, MVTX, and the readiness for procurement of the Staves and Readout Units.

In carrying out its charge, the review committee is requested to evaluate the following specific items:

- Does the current design demonstrate that the MVTX Staves and Readout Units will be compliant with its specifications?
- Can the data from MVTX staves be extracted, readout and integrated into sPHENIX Data Acquisition System?
- Are the electrical interfaces of the Staves and Readout Units to other sPHENIX components at a proper level of understanding?
- 4. Has the responsibility for fabrication, tests and acceptance for the Staves and Readout Units been defined?
- 5. Has a QA plan and acceptance tests for the Staves and Readout Units been clearly defined and documented?
- 6. Has the inspection/test records archive plan been clearly defined and is the information easily accessible?
- 7. Is the design of the Staves and Readout Units final?
- 8. Are the Staves and Readout Units ready for procurement?

The review committee is also requested to evaluate the following specific items concerning the maturity of the design and its integration within sPHENIX:

- Status of the simulation to optimize the MVTX and INTT for tracking in sPHENIX and timescale for its completion
- Status of the mechanical integration between the MVTX, INTT and other sPHENIX components and timescale for a final design

Reviewers may additionally, at their discretion, comment on any other notable issues and/or concerns which they identify.

A report from the committee is expected to be submitted to me by July 27, 2018.

I very much appreciate you willingness to lend your time and expertise in this important process and look forward to receiving your assessment.

len : he Kunde

Berndt Mueller Associate Laboratory Director for Nuclear and Particle Physics Brookhaven National Laboratory




Presentations from all

- Yes!
 - Acceptance
 - Readout speed
 - Spatial resolution
 - Hit efficiency
 - Noise and occupancy
 - Radiation tolerance

Item	Requirement
Acceptance	Vertex $ z < 10$ cm, $ \eta < 1$, full azimuthal coverage
Readout speed	Matching the sPHENIX DAQ 15 kHz event trigger rate
DCA resolution	$< 50 \ \mu m$ for charged pions at $p_T = 1 \ \text{GeV}/c$
Tracking efficiency	> 80% efficiency for charged pions at $p_T = 1 \text{ GeV}/c$ in the 10% most cen-
- •	tral Au+Au collisions

Table 1: Summary for the vertex detector requirements




July 19-20, 2018



Sho, Alex, Jo

- Yes! •
 - Test beam online monitoring and data analysis have been carried out in the sPHENIX online and offline framework



Online display:


July 19-20, 2018

July 19-20, 2018

MVTX Director's Review



- We have exercised the full readout chain and controls at Fermilab test beam





Sho, Alex, Jo



Leo & Jo

Yes! •

12. Creative Odumica / DNI

- ALICE/CERN will produce staves and RU for sPHENIX. —
- sPHENIX/MVTX group will perform the acceptance test and QA in US. —

Detector-Specific Quality Assurance Plan	Detector-Specific Quality Assurance Plan
for MVTX Stave Acceptance/Detector Construction	For MVTX Readout Unit Production/Acceptance For the sPHENIX Project
for the sPHENIX Experiment at RHIC	Physics Department University of Texas Austin, Texas
Lawrence Berkeley National Laboratory Berkeley, CA	Revision 1.0 July 2, 2018
	sPHENIX Project
Revision 1.0	DETECTOR-SPECIFIC QUALITY ASSURANCE PLAN
July 4, 2018	Approved by:
sPHENIX Project	Josebin J. Schambach Date Date
DETECTOR-SPECIFIC QUALITY ASSURANCE PLAN	Accepted by:
	Edward OBrien Date ePHENX Project Director Brochaven Visional Laboratory
	James Mills sPHENX Project Managor - Engineering Brochswn National Laboratory
	Glienn Young Date aPHENX Project Manager Brochtaven National Laboratory
PHENIX Detector QAP: MVTX Stave Acceptance/Detector Construction Rev 1.01 of 20	sPHENIX Detector QAP: Readout Unit Production Rev 1.0 1 of

July 19-20, 2018

#5, Has a QA plan and acceptance tests for the Staves and Readout Units been defined?



Leo & Jo

- Yes! •
 - Both stave and RU QAP documents are available. _

Detector-Specific Quality Assurance Plan for MVTX Stave Acceptance/Detector Construction for the sPHENIX Experiment at RHIC Lawrence Berkeley National Laboratory Berkeley, CA	Detector-Specific Quality Assurance Plan For MVTX Readout Unit Production/Acceptance For the sPHENIX Project Physics Department University of Texas Austin, Texas Revision 1.0 July 2, 2018 SPHENIX Project
Revision 1.0 July 4, 2018	DETECTOR-SPECIFIC QUALITY ASSURANCE PLAN Approved by:
sPHENIX Project	Joachim J. Schambach Date sPHENIX L3 Manager for MVTX RU production University of Texas at Austin
DETECTOR-SPECIFIC QUALITY ASSURANCE PLAN	Accepted by: Edward O'Brien Date SPHENIX Project Director Brockhaven National Laboratory
	James Mills sPHENIX Project Manager - Engineering Brookhaven National Laboratory
sPHENIX Detector QAP: MVTX Stave Acceptance/Detector Construction Rev 1.01 of 20	Glenn Young Date sPHENIX Project Manager Brookhaven National Laboratory
	sPHENIX Detector QAP: Readout Unit Production Rev 1.0 1 of 12

1 of 13

#6, Has the inspection/test records archive plan been defined and is the information easily accessible?

• Yes!

Iddd clocked

Idda clocked

Max. bias voltage

FIFO exceptions

Corrupt events

Bad pixels per chip

Dead pixels per chip

Deviation of chip threshold

Average HIC noise

Threshold RMS

Pixels without threshold per chip

Threshold RMS / Threshold mean

Ibb @ 3V

FIFO errors

Timeouts

Parameter

Follow the same QA procedures being used for ALICE ITS/IB production at CERN

< 5243

< 52429

< 5243

Otherwise

Otherwise

< 0.5

- Use ALICE DB for initial sPHENIX production
- Move to sPHENIX DB later when available

otherwise

otherwise

otherwise

-

< 2100

< 26214

< 2100

Otherwise

< 30%

500 to 850 mA

120 to 250 mA

Up to 10 mA

4V

0

0

< 50

< 5243


< 50

< 10 e

< 20%

< 30 e

< 0.3



Otherwise

Otherwise

Otherwise

Otherwise

Otherwise

Otherwise

Otherwise

Otherwise

Otherwise

→ Power Test

→ FIFO Test

→ Digital Scan

→ Threshold Scan



Leo & Jo



Leo & Jo


Stave: Yes!

- Minor modification of power extension cable for FPC, MVTX 35cm cables (ALICE, 15cm)
- ALICE ITS/IB staves production in progress

RU: Yes!

- Pre-production boards (v2.0) being tested at CERN
- ALICE ITS RU production follows after the test.









Leo, Jo, Walt

- Staves: Yes!
 - High-speed line, no change
 - Longer (15cm ->35cm) power extension cables, Prototype power extension cables produced at LANL for testing.

- RU: Yes!
 - Once the final v2 pre-production boards pass the test, full production will proceed
 - RU v1 meets readout integration requirements








Tony, Dave & Gunther

- All essential sPHENIX simulation tools are available to verify tracking performance with various layers of INTT configurations
- A simulation task force formed, with charge and targeted due date





Walt & Dan

- sPHENIX Office of System Integration coordinates integration effort
- Significant progress on the integration in the past few months the integration issues of inner tracking system appear manageable
- Detailed 3-D models being developed, a physical mock-up to confirm the final design

