

# Run 12 200GeV Online Local Polarimetry


Sanghwa Park, Josh Perry, Ciprian Gal

February 22, 2012


## Classical Local Pol

- ▶ Offline analysis with data from DAQ ( 200 Hz during normal running time)
- ▶ Useful because we can make energy cuts and eliminate a large amount of background
- ▶ We calculate a raw asymmetry (and  $A_N$ ) as a function of  $\phi$

## Results for Blue $A_N$




## Results for Yellow $A_N$




## Scaler Local Pol

- ▶ We use the Shower Max Detector in the ZDC to get scaler counts for each crossing every 5 minutes (L,R,U,D)
- ▶ Does not use DAQ bandwidth
- ▶ Has a fast return rate (the analysis is integrated in the PHENIX online monitoring and is done automatically)
- ▶ We cannot make energy cut on the ZDC and it is sensitive to backgrounds (the  $A_N$  is diluted by backgrounds giving us a smaller asymmetry) (we are working to gate this with the ZDC coincidence)



## Scaler counts/BBCnoVtx with bad points



## Scaler counts/BBCnoVtx



## Raw asymmetry for fill 16449





- ▶ We will use both of these methods to get a  $< 5\%$  transverse component at PHENIX
- ▶ We need:
  - ▶ 1 fill of transverse beam
  - ▶ 1 fill of rotator commissioning with the Scalars (we would like to be at MCR so that we can give fast feedback to the person responsible with setting Rotator magnet currents)
  - ▶ 1 fill of longitudinal beam (to confirm small transverse component)
- ▶ For the rotator settings we would suggest starting with the run12 settings (from the 5 we tried the last settings had the lowest transverse component)

- ▶ The Classical method shows that the  $A_N$  as we measure is stable for both blue and yellow beams
- ▶ We are making progress in understanding our scalars (and plan to improve them soon)
- ▶ As expected we can see the scalar counts have some luminosity dependence (we are going to extract a systematic from it)
- ▶ We are working on getting a decay parameter for the polarization
- ▶ Fully ready for rotator commissioning